


SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:				FUNDING: 80% FED : 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004 ROADWAY	0011 SN 008-0014 (EX) SN 008-0051 (PR)
28100105	STONE RIPRAP, CLASS A3	SQ YD	68	68	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1168		1168
28200200	FILTER FABRIC	SQ YD	1236	68	1168
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	4888	4888	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	292	292	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	329	329	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	497	497	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	322	322	
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	2161	2161	
44000100	PAVEMENT REMOVAL	SQ YD	317	317	
44004250	PAVED SHOULDER REMOVAL	SQ YD	507	507	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1393	1393	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	120		120

SPECIALTY ITEMS

FILE NAME #	USER NAME # USER#	DESIGNED - RAC	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	 <p>Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60613</p>	<p align="center">SUMMARY OF QUANTITIES</p>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE#		DRAWN - SAW	REVISED -				646	5 BR-3	CARROLL	84	6
PLOT SCALE # SCALE#		CHECKED - DAZ	REVISED -				CONTRACT NO. 64084		ILLINOIS FED. AID PROJECT		
PLOT DATE # DATE#		DATE - 10-11-13	REVISED -				SCALE:	SHEET 2 OF 6 SHEETS	STA. TO STA.		