

GENERAL NOTES

Temporary Impact Attenuators will be measured as each for each attenuator supplied on the job as specified in the plans, and shall include the cost of renting/owning the attenuator for the time required on the job plus hauling to and from the project site, as well as one placement and removal from the roadway. This shall be paid for at the contract unit price per Each for IMPACT ATTENUATORS, TEMPORARY of the type specified.

Relocate Temporary Impact Attenuators will be paid for as Each and will be paid for each time the attenuator is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Each for IMPACT ATTENUATORS, RELOCATE of the type specified.

This work shall be done in accordance with Section 704 of the Standard Specifications. Temporary Concrete Barrier will be measured in feet along the centerline of the barrier and shall include the cost of renting/owning the barrier for the time required on the job plus hauling to and from the project site, as well as one placement and removal from the roadway in accordance with Section 704 of the Standard Specification. This shall be paid for at the contract unit price per Foot for TEMPORARY CONCRETE BARRIER.

Relocate Temporary Concrete Barrier will be paid for in Feet along the centerline of the barrier, and will be paid for each time the barrier is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Foot for RELOCATE TEMPORARY CONCRETE BARRIER.

Tree planting layout shall be performed by the District Roadside Management Specialist. Mulch shall be placed 4" thick and to the diameter around the tree as shown on District Standard 92.1. The mulch shall be hardwood wood chips placed on weed barrier fabric. This work shall be included in the cost of the tree.

Excess trees that cannot be planted along the IL 78/Canyon Road project limits shall be planted at alternative locations as determined by the District Roadside Management Specialist.

FILE NAME = 64F74.GHD00X	USERNAME =	DESIGNED - Engineering Systems	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	CHECKED -	REVISED -			FAP 650/FAS 74	104T-3	JoDeVries	97	5
	FLOT DATE = 10/02/2013 6:34 AM	DATE = 10/02/2013 9:12 AM	REVISED -			(IL 78/Canyon Rd.)	CONTRACT NO. 64F74		ILLINOIS	
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.						