SCHEDULE OF QUANTITIES

66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS

EACH	LOCATION			
	IL 78			
1.0	Sta	908 +50		57.64' LT
1.0	Sta	912 +00		55.00' LT
1.0	Sta	912 +10		80.00' LT
1.0	Sta	912 +40		80.00' LT
1.0	Sta	912 +50		55.00' LT
1.0	Sta	914 +00		55.00' LT
1.0	Sta	915 +00		40.00' LT
1.0	Sta	908 +06		60.00' RT
1.0	Sta	909 +00		60.00' RT
1.0	Sta	911 +00		60.00' RT
1.0	Sta	912 +00		70.00' RT
1.0	Sta	912 +50		70.00' RT
1.0	Sta	915 +00		47.36' RT
1.0	Sta	1095 +35		53.76' LT
1.0	Sta	1096 +50		135.00' LT
1.0	Sta	1097 +00		135.00' LT
1.0	Sta	1097 +50		90.00' LT
1.0	Sta	1098 +25		49.42' LT
1.0	Sta	1094 +50		50.00' RT
1.0	Sta	1095 +00		75.00' RT
1.0	Sta	1095 +50		85.00' RT
1.0	Sta	1096 +00		110.00' RT
1.0	Sta	1096 +50		110.00' RT
1.0	Sta	1097 +00		80.00' RT
1.0	Sta	1097 +60		64.28' RT
	Canyon Rd			
1.0	Sta	103 +00		40.00' LT
1.0	Sta	104 +00		50.00' LT
1.0	Sta	104 +50		50.00' LT
1.0	Sta	105 +25		85.00' LT
1.0	Sta	107 +00		85.00' LT
1.0	Sta	109 +25		35.00' LT
1.0	Sta	103 +00		40.00' RT
1.0	Sta	104 +00		50.00' RT
1.0	Sta	105 +00		50.00' RT
1.0	Sta	105 +75		100.00' RT
1.0	Sta	106 +75		100.00' RT
1.0	Sta	107 +50		40.00' RT
1.0	Sta	118 +50		35.00' LT
1.0	Sta	119 +30		70.00' LT
1.0	Sta	119 +70		70.00' LT
1.0	Sta	120 +75		35.00' LT
1.0	Sta	118 +50		35.00' RT
1.0	Sta	118 +90		45.00' RT
1.0	Sta	119 +20		95.00' RT
1.0	Sta	119 +85		55.00' RT
1.0	Sta	120 +10		95.00' RT
1.0	Sta	120 +50		35.00' RT
47.0	TOTAL			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	
	IL78	
1.0	As Directed by the Resident and Coordination with Surveys	043–1098
1.0	As Directed by the Resident and Coordination with Surveys	043–1097
	Canyon Rd	
1.0	As Directed by the Resident and Coordination with Surveys	043–1099
1.0	As Directed by the Resident and Coordination with Surveys	043–C001
4.0	TOTAL	

70106700 TEMPORARY RUMBLE STRIPS

EACH	LOCATION
	IL 78
6.0	As required per Standard 701321
6.0	TOTAL

70300100 SHORT TERM PAVEMENT MARKING

FOOT	LOCATION					
	IL78					
30.0	Sta	908 +00	–	915 +50		White Shoulder LT
30.0	Sta	908 +00	–	915 +50		White Shoulder RT
82.0	Sta	907 +25	–	916 +25		Yellow Centerline
18.0	Sta	1094 +00	–	1098 +50		White Shoulder LT
18.0	Sta	1094 +00	–	1098 +50		White Shoulder RT
53.0	Sta	1093 +33	–	1099 +18		Yellow Centerline
	Canyon Rd					
55.0	Sta	103 +25	–	109 +25		Yellow Centerline
23.0	Sta	118 +25	–	120 +77		Yellow Centerline
309.0	TOTAL					

70300220 TEMPORARY PAVEMENT MARKING – LINE 4"

FOOT	LOCATION					
	IL78					
611.0	Sta	909 +56	–	915 +65		Stage I LT
392.0	Sta	910 +54	–	914 +46		Stage I RT
353.0	Sta	910 +51	–	914 +04		Stage II LT
612.0	Sta	908 +91	–	915 +01		Stage II RT
1968.0	TOTAL					

70300280 TEMPORARY PAVEMENT MARKING – LINE 24"

FOOT	LOCATION	
	IL78	
12.0	Sta	908 +81
12.0	Sta	915 +75
24.0	TOTAL	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION					
	IL78					
10.0	Sta	908 +00	–	915 +50		White Shoulder LT
10.0	Sta	908 +00	–	915 +50		White Shoulder RT
27.3	Sta	907 +25	–	916 +25		Yellow Centerline
6.0	Sta	1094 +00	–	1098 +50		White Shoulder LT
6.0	Sta	1094 +00	–	1098 +50		White Shoulder RT
17.7	Sta	1093 +33	–	1099 +18		Yellow Centerline
203.5	Sta	909 +56	–	915 +65		Stage I LT
130.5	Sta	910 +54	–	914 +46		Stage I RT
117.6	Sta	910 +51	–	914 +04		Stage II LT
203.8	Sta	908 +91	–	915 +01		Stage II RT
	Canyon Rd					
18.3	Sta	103 +25	–	109 +25		Yellow Centerline
7.7	Sta	118 +25	–	120 +77		Yellow Centerline
758.4	TOTAL					

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
	IL78				
325.0	Sta	910 +79	–	913 +88	Stage I
325.0	TOTAL				

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
	IL78				
325.0	Sta	910 +64	–	913 +85	Stage II
325.0	TOTAL				

X - FAP 650 & FAS 74

FILE NAME = c:\pw_work\pwidot\rundbladerrr\d0232736\D201310-sht-schedule.dgn	USER NAME = rundbladerr	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 80.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = Thu Oct 10 07:02:46 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 78 /CANYON RD.
SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
X	104T-3	JO DAVIESS	97	23

CONTRACT NO. 64F74

ILLINOIS FED. AID PROJECT