

SCHEDULE OF QUANTITIES

70600250 IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	IL78
1.0	Sta 910 +60 Stage I
1.0	Sta 913 +99 Stage I
<u>2.0</u>	TOTAL

70600350 IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION
	IL78
1.0	Sta 910 +53 Stage II
1.0	Sta 913 +96 Stage II
<u>2.0</u>	TOTAL

78001110 PAINT PAVEMENT MARKING- LINE 4"

FOOT	LOCATION
900	STATION 907 +25 TO 916 +25 WHITE SHOULDER LT
900	STATION 907 +25 TO 916 +25 WHITE SHOULDER RT
116	STATION 907 +25 TO 911 +89 YELLOW CENTERLINE
545	STATION 911 +89 TO 916 +25 YELLOW CENTERLINE No Passing NB
585	STATION 1093 +50 TO 1098 +50 WHITE SHOULDER LT
585	STATION 1093 +50 TO 1098 +50 WHITE SHOULDER RT
71.25	STATION 1093 +50 TO 1094 +07 YELLOW CENTERLINE No Passing SB
110.75	STATION 1094 +07 TO 1098 +50 YELLOW CENTERLINE
600	STATION 103 +25 TO 109 +25 WHITE SHOULDER LT
600	STATION 103 +25 TO 109 +25 WHITE SHOULDER RT
1200	STATION 103 +25 TO 109 +25 YELLOW CENTERLINE SB and NB No Passing Zone
252	STATION 118 +25 TO 120 +77 WHITE SHOULDER LT
252	STATION 118 +25 TO 120 +77 WHITE SHOULDER RT
<u>315</u>	STATION 118 +25 TO 120 +77 YELLOW CENTERLINE NB No Passing Zone
<u>7032</u>	
14064	TOTAL (2 COATS)

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION
	IL78
8.0	Sta 907 +25 - 916 +25
11.0	Sta 1093 +33 - 1099 +18
<u>19.0</u>	TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION
	IL78
130.5	Sta 910 +54 -914 +46 Stage I - White Shoulder LT
13.7	Sta 908 +91 -910 +56 Stage I - Yellow Centerline Dash
14.5	Sta 914 +01 -915 +75 Stage I - Yellow Centerline Dash
55.0	Sta 908 +91 -910 +56 Stage I - Yellow Centerline Solid
58.0	Sta 914 +01 -915 +75 Stage I - Yellow Centerline Solid
<u>117.2</u>	Sta 910 +51 -914 +03 Stage II - White Shoulder LT
388.9	TOTAL

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION
	IL78
8.0	Sta 907 +25 - 916 +25
11.0	Sta 1093 +33 - 1099 +18
<u>19.0</u>	TOTAL

X4400110 TEMPORARY PAVEMENT REMOVAL

SQ YD	LOCATION
212.1	910 +30.5 to 914 +04

X5430100 INSERTION CULVERT LINER (SPECIAL)

FOOT	LOCATION
123	CULVERT 043-1097

Z0025505 PROPERTY MARKERS

EACH	LOCATION
	IL 78
8.0	As Needed & Directed by the Resident Engineer
<u>8.0</u>	TOTAL

Z0026407 TEMPORARY SHEET PILING

SQ YD	LOCATION
770	SEE STAGING

Z0049300 REFERENCING LAND SECTION MARKERS

EACH	LOCATION
1	STATION 120 +87

Z0054500 ROCK FILL

TON	LOCATION
202.95	CULVERT 043-1098 (STATION 912 +26)
78.105	CULVERT 043-1097 (STATION 1096 +26)
265.065	CULVERT 043-C001 (STATION 105 +93)
<u>144.853</u>	CULVERT 043-1099 (STATION 119 +63)
690.973	TOTAL

Z0062456 TEMPORARY PAVEMENT

SQ YD	LOCATION
212.1	910 +30.5 TO 914 +04

Z0073002 TEMPORARY SOIL RETENTION SYSTEM

SQ FT	LOCATION
48	912 +09 TO 912 +42 3'X16'

X - FAP 650 & FAS 74

FILE NAME =	USER NAME = rundbladerr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 78 /CANYON RD. SCHEDULE OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\rundbladerr\d0232736	D201310-sh-t-schedule.dgn	DRAWN -	REVISED -			X	104T-3	JO DAVIESS	97	24
	PLOT SCALE = 80.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 64F74				
	PLOT DATE = Thu Oct 10 07:02:59 2013	DATE -	REVISED -			SCALE:	SHEET OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT		