

URBAN  
100% STATE

CODE NUMBER	ITEM	0014 STATE FUNDS	
		UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	93
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	167
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	60
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	45
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	366
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	134
50102400	CONCRETE REMOVAL	CU YD	1.9
50300225	CONCRETE STRUCTURES	CU YD	2.6
50300260	BRIDGE DECK GROOVING	SQ YD	345
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5,090
50800515	BAR SPLICERS	EACH	80
50901050	STEEL RAILING, TYPE SM	FOOT	146
52000110	PREFORMED JOINT STRIP SEAL	FOOT	45
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	25
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	400
63500105	DELINEATORS	EACH	4
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2

23

NOTE: \* SPECIALTY ITEMS

\*\* ESTIMATED QUANTITIES. ACTUAL QUANTITIES TO BE DETERMINATED BY RESIDENT ENGINEER

URBAN  
100% STATE

CODE NUMBER	ITEM	0014 STATE FUNDS	
		UNIT	TOTAL QUANTITY
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	48
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	798
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,236
70400100	TEMPORARY CONCRETE BARRIER	FOOT	380.1
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	316.8
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2,858
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	10
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	572
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9
X0326519	STEEL RAILING REMOVAL	FOOT	146
X0964700	SHOULDERS SPL	SQ YD	216
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	135
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	934
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	366
** Z0003700	BEARING PAD ADJUSTMENT	EACH	16
* <del>Z0004540</del>	<del>HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE</del>	<del>SQ YD</del>	<del>366</del>
** Z0017300	DOWEL REPAIR	EACH	32
** Z0032700	KEYWAY REPAIR	FOOT	250

23

Rev. 12-26-13