

20200100 EARTH EXCAVATION					
CU YD	LOCATION				OFFSET
	IL 92				
93	Sta	1236 +47	-	1237 + 22	LT, RT
93	TOTAL				

30300112 AGGREGATE SUBGRADE IMPROVEMENT 12"					
SQ YD	LOCATION				OFFSET
	IL 92				
167	Sta	1236 +47	-	1237 + 22	LT, RT
167	TOTAL				

40603340 HOT-MIX ASPHALT SURFACE COURSE MIX "D", N70					
TON	LOCATION				OFFSET
	IL 92				
30	Sta	1237 +22	-	1238 + 22	
30	Sta	1238 +98.7	-	1239 + 98.7	
60	TOTAL				

40603310 HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50					
TON	LOCATION				OFFSET
	IL 92				
15	Sta	1236 +47	-	1237 + 22	LT,RT
15	Sta	1237 +22	-	1238 + 22	LT,RT
15	Sta	1238 +98.7	-	1239 + 98.7	LT,RT
45	TOTAL				

48203021 HOT-MIX ASPHALT SHOULDER 6"					
SQ YD	LOCATION				OFFSET
	IL 92				
134	Sta	1236 +47	-	1237 + 22	LT,RT
134	TOTAL				

50102400 CONCRETE REMOVAL					
CU YD	LOCATION				OFFSET
	IL 92				
1.9	Sta,	1238 +22	-	1238 + 98.7	
1.9	TOTAL				

50300225 CONCRETE STRUCTURES					
CU YD	LOCATION				OFFSET
	IL 92				
0.65	At Sta,	1238 +22			
0.65	At Sta,	1238 +98.7			
1.3	TOTAL				

50300260 BRIDGE DECK GROOVING					
SQ YD	LOCATION				OFFSET
	IL 92				
345	Sta	1238 +22	-	1238 + 98.7	
345	TOTAL				

50300205 REINFORCEMENT BARS, EPOXY COATED					
POUND	LOCATION				OFFSET
	IL 92				
5,090	Sta	1238 +22	-	1238 + 98.7	
5,090	TOTAL				

50800515 BAR SPLICERS					
EACH	LOCATION				OFFSET
	IL 92				
80	Sta	1238 +22	-	1238 + 98.7	
80	TOTAL				

50901050 STEEL RAILING, TYPE SM					
FOOT	LOCATION				OFFSET
	IL 92				
73	Sta	1238 +23.85	-	1238 + 96.85	LT
73	Sta	1238 +23.85	-	1238 + 96.85	RT
146	TOTAL				

52000110 PREFORMED JOINT STRIP SEAL					
FOOT	LOCATION				OFFSET
	IL 92				
45	At Sta,	1238 +22			
45	TOTAL				

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS					
FOOT	LOCATION				OFFSET
	IL 92				
12.5	Sta	1239 +42.45	-	1239 + 54.95	LT
12.5	Sta	1237 +65.75	-	1237 + 78.25	RT
25.0	TOTAL				

63100087 TRAFFIC BARRIER TERMINAL TYPE 6A					
EACH	LOCATION				OFFSET
	IL 92				
1	Sta	1237 +78.25	-	1238 + 22	LT
1	Sta	1238 +98.7	-	1239 + 42.45	LT
1	Sta	1237 +78.25	-	1238 + 22	RT
1	Sta	1238 +98.7	-	1239 + 42.45	RT
4	TOTAL				

63100167 TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT					
EACH	LOCATION				OFFSET
	IL 92				
1	Sta	1237 +28.25	-	1237 + 78.25	LT
1	Sta	1237 +15.75	-	1237 + 65.75	LT
1	Sta	1239 +54.95	-	1240 + 04.95	RT
1	Sta	1239 +42.45	-	1239 + 92.45	RT
4	TOTAL				

63200310 GUARDRAIL REMOVAL					
FOOT	LOCATION				OFFSET
	IL 92				
100	Sta	1237 +22	-	1238 + 22	LT
100	Sta	1238 +98.7	-	1239 + 98.7	LT
100	Sta	1237 +22	-	1238 + 22	RT
100	Sta	1238 +98.7	-	1239 + 98.7	RT
400	TOTAL				

63500105 DELINEATORS					
EACH	LOCATION				OFFSET
	IL 92				
1	At Sta	1237 +28.25			LT
1	At Sta	1240 +04.95			LT
1	At Sta	1237 +15.75			RT
1	At Sta	1239 +92.45			RT
4	TOTAL				

70300100 SHORT TERM PAVEMENT MARKING					
FOOT	LOCATION				OFFSET
	IL 92				
FINAL SURFACE 28	Sta	1237 +22	-	1239 + 98.7	
MILLED SURFACE 20	Sta	1237 +22	-	1239 + 98.7	
48	TOTAL				

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"					
FOOT	LOCATION				OFFSET
	IL 92				
13	Sta	1234 +97			RT
13	Sta	1242 +48			LT
26	TOTAL				

70301000 WORK ZONE PAVEMENT MARKING REMOVAL					
SQ FT	LOCATION				OFFSET
	IL 92				
STAGE 1 387					
STAGE 2 411					
798	TOTAL				

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

Schedule of Quantities

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	D2 DECK REPAIR 2014-1	ROCK ISLAND	16	4
CONTRACT NO. 64J90				