

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FED 90% STATE 10% ROADWAY	FED 90% STATE 10% ROADWAY
				0004 RURAL	0004 URBAN
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	35813	8997	28816
48101200	AGGREGATE SHOULDERS, TYPE B	TON	459	37	422
48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	14964	3804	11160
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4163	1080	3083
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	---	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	---	1
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	---	1
50105220	PIPE CULVERT REMOVAL	FOOT	6159	1441	4718
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	93	---	93
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	---	2
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	---	2
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	2	---	2
54010302	PRECAST CONCRETE BOX CULVERTS 3' X 2'	FOOT	63	---	63
54011204	PRECAST CONCRETE BOX CULVERTS 12' X 4'	FOOT	59	---	59

* SPECIALTY ITEM

FILE NAME * 0360905-SHT-500.DGN	USER NAME * --	DESIGNED - JKC	REVISED - -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE * NONE	CHECKED - JKC	REVISED - -	REVISED - -					41	111W&RS-1	KANKAKEE	450	5
PLOT DATE * 07/13	DATE - 07/13	REVISED - -	REVISED - -		SCALE: NONE	SHEET	OF	SHEETS	STA. -	TO STA. -	CONTRACT NO. 66905	
ILLINOIS FED. AID PROJECT												