

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FED 90% STATE 10% ROADWAY	FED 90% STATE 10% ROADWAY
				0004	0004
				RURAL	URBAN
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	200	139	61
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	148	148	---
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	131	66	65
542D5470	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"	FOOT	180	---	180
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	261	---	261
542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	138	---	138
542D5485	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	65	---	65
54213450	END SECTIONS 15"	EACH	20	10	10
54213453	END SECTIONS 18"	EACH	14	8	6
54213456	END SECTIONS 21"	EACH	6	4	2
54213459	END SECTIONS 24"	EACH	16	8	8
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	2	5
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	42	9	33
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	---

* SPECIALTY ITEM

FILE NAME * 0366905-SHT-500.DGN	USER NAME * --	DESIGNED - JKC	REVISED - -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FL07 SCALE * NONE	CHECKED - JKC	REVISED - -	41					(11)W&RS-1	KANKAKEE	450	8	
PL07 DATE * 07/13	DATE - 07/13	REVISED - -	SCALE: NONE SHEET ___ OF ___ SHEETS STA. - TO STA. -			ILLINOIS FED. AID PROJECT						
CONTRACT NO. 66905												