

80% FEDERAL
20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				PUTNAM	PUTNAM	PUTNAM
				COUNTY	COUNTY	COUNTY
				ROADWAY	S. N. 078-2500	S. N. 078-2007
				0004	0040	0040
M2810225	STONE RIPRAP, CLASS B3	M TON	176	176		
M2820200	FILTER FABRIC	SO M	1317	1192		125
M3111150	SUB-BASE GRANULAR MATERIAL, TYPE B 150 MM	SO M	321	321		
M3550450	HOT-MIX ASPHALT BASE COURSE, 150MM	SO M	101	101		
M3560500	HOT-MIX ASPHALT BASE COURSE WIDENING, 200MM	SO M	543	543		
M4060215	POLYMERIZED BITUMINOUS MATERIAL (PRIME COAT)	M TON	1	1		
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO M	409	409		
M4060990	TEMPORARY RAMPS	SO M	48	48		
M4062125	LEVELING BINDER (MACHINE METHOD), N50	M TON	95	95		
M4063335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	M TON	201	201		
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	12.1	12.1		
M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SO M	814	814		
M4402010	DRIVEWAY PAVEMENT REMOVAL	SO M	104	104		
M4428440	CLASS D PATCHES, TYPE IV, 300MM	SO M	321	321		

FILE NAME * plot.dgn	USER NAME * aubr-eggs	DESIGNED - DRAWN -	REVISED - REVISED -
PLOT SCALE * 100.0000 H / in.	CHECKED -	REVISED -	REVISED -
PLOT DATE * 3/29/2013	DATE -	REVISED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

P.A.P. RATE 619	SECTION I20BR.CR	COUNTY PUTNAM	TOTAL SHEETS 77	SHEET NO. 12
CONTRACT NO. 68740			ILLINOIS FED. AID PROJECT	