

80% FEDERAL
20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				PUTNAM	PUTNAM	PUTNAM
				COUNTY	COUNTY	COUNTY
				ROADWAY	S. N. 078-2500	S. N. 078-2007
				0004	0040	0040
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	43	43		
M5010522	PIPE CULVERT REMOVAL	METER	16	16		
M5030360	CONCRETE SUPERSTRUCTURE	CU M	7.1		3	4.1
M5080105	REINFORCEMENT BARS	KG	870			870
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	16,740		450	16,290
M5090540	PIPE HANDRAIL	METER	32.8	32.8		
M5401100	PRECAST CONCRETE BOX CULVERT 2.4M X 1.5M	METER	21.5		21.5	
M5403000	CONCRETE BOX CULVERTS	CU M	149.8			149.8
M5422345	PIPE CULVERTS, CLASS A, TYPE I EQUIVALENT ROUND-SIZE 1200MM	METER	8.5	8.5		
M542F020	METAL END SECTIONS 450MM	EACH	2	2		
M542H430	PIPE CULVERTS, CLASS D, TYPE I 450MM	METER	17.2	17.2		
M6320030	GUARDRAIL REMOVAL	METER	350	350		
M7030100	SHORT-TERM PAVEMENT MARKING	METER	78	78		
* M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	1092	1092		
* M7030580	PAVEMENT MARKING TAPE, TYPE III 600MM	METER	16	16		

15

*SPECIALTY ITEM

FILE NAME * plandgn	USER NAME * aubraygn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			619	120BR.CR	PUTNAM	77	13	
		CHECKED -	REVISED -			CONTRACT NO. 68740					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
		PLOT SCALE * 100.0000 M / in.									
		PLOT DATE * 3/29/2013									