

CONTRACT #68740

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
619	120BR,CR	PUTNAM	77	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY CONCRETE BARRIER				
LOCATION		LENGTH (METERS)	NOTES	
12+008.3	TO 12+103.1	95	STAGE 2	
12+476.3	TO 12+582.8	107	STAGE I	
12+521.24	TO 12+532.84	11	PRE-STAGE I/STAGE I	
TOTAL		213		

RELOCATE TEMPORARY CONCRETE BARRIER				
LOCATION		LENGTH (METERS)	NOTES	
12+008.3	TO 12+103.1	95	STAGE 3	
12+484	TO 12+575.2	92	STAGE II	
TOTAL		187		

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321		
LOCATION	EACH	
S.N. 078-2500	1	
S.N. 078-2007	1	
TOTAL	2	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		
LOCATION	L. SUM	
S.N. 078-2500	0.5	
S.N. 078-2007	0.5	
TOTAL	1	

TRAFFIC CONTROL SURVEILLANCE		
LOCATION	CAL DAY	
JOBSITE	5	
TOTAL	5	

PERMANENT SURVEY MARKERS, TYPE 1	
LOCATION	EACH
POT STA. 12+038.014	1
POT STA. 12+242.399	1
STA. 12+530, S.N. 078-2007	1
POT STA. 12+587.632	1
TOTAL	4

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
STA. 12+002.9 TO STA. 12+106	4
STA. 12+476 TO STA. 12+600	5
TOTAL	9

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
STA. 12+002.9 TO STA. 12+106	4
STA. 12+476 TO STA. 12+600	5
TOTAL	9

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL MO
JOBSITE	2
TOTAL	2

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA. 12+007	1
STA. 12+104	1
STA. 12+475	1
STA. 12+583	1
TOTAL	4

IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA. 12+007	1
STA. 12+104	1
STA. 12+475	1
STA. 12+583	1
TOTAL	4

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1

PAVEMENT MARKING REMOVAL	
LOCATION	AREA
	SQ. M
CULVERT AT STA. 12+058.5	28
CULVERT AT STA. 12+530	49
TOTAL	77.2

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
LOCATION	L. SUM
S.N. 078-2500	0.5
S.N. 078-2007	0.5
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, STANDARD BLR-22	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1

WORKZONE PAVEMENT MARKING REMOVAL	
LOCATION	AREA (SQ. M)
STA. 11+949 TO STA. 12+153	57
STA. 12+350 TO STA. 12+651	61
TOTAL	119

MODIFIED URETHANE PAVEMENT MARKING - LINE 100mm			
STATION TO STATION	YELLOW SKIP-DASH 4"	YELLOW SOLID 4"	WHITE SOLID 4"
	(METER)	(METER)	(METER)
12+003 TO 12+106	26	49	206
12+476 TO 12+600	31	20	248
TOTAL	57	69	454
GRAND TOTAL	580		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p style="text-align: center;">SCHEDULE OF QUANTITIES</p> <p style="text-align: right;">DRAWN BY CHECKED BY</p>