

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				0021 SAFETY	0021 TRAFFIC SIGNAL	0021 OVERHEAD LIGHTING	0004 ROADWAY	0004 ROADWAY	0004 ROADWAY	
				90% FED 10% STATE	90% FED 6.7% STATE 3.3% CITY	100% CITY	80% FED 20% STATE	80% STATE 20% CITY	100% STATE	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	240				120	120		
28000315	AGGREGATE DITCH CHECKS	TON	9				9			
28000500	INLET AND PIPE PROTECTION	EACH	6				6			
28000510	INLET FILTERS	EACH	13				13			
28100105	STONE RIPRAP, CLASS A3	SQ YD	43				36	7		
28100107	STONE RIPRAP, CLASS A4	SQ YD	231				231			
28200200	FILTER FABRIC	SQ YD	274				267	7		
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	115	115						
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2161	2161						
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	1801	1801						
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	94	94						
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	49				49			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	85				85			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	4.7	4.7						

X SPECIALTY ITEM

FILE NAME : c:\pwork\pedit\aubreygs\0310674\046	USER NAME : aubreygs	DESIGNED : -	REVISED : -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 6658	SECTION ION	COUNTY PEORIA	TOTAL SHEETS 120	SHEET NO. 5
PLOT SCALE : 100.0000' / 1"	DRAWN : -	CHECKED : -	REVISED : -			CONTRACT NO. 68A70				
PLOT DATE : 10/16/2013	DATE : -	REVISED : -	ILLINOIS FED. AID PROJECT							