

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				0021 SAFETY	0021 TRAFFIC SIGNAL	0021 OVERHEAD LIGHTING	0004 ROADWAY	0004 ROADWAY	0004 ROADWAY								
				90% FED	90% FED	100% CITY	80% FED	80% STATE	100% STATE								
				10% STATE	6.7% STATE		20% STATE	20% CITY									
40600895	CONSTRUCTING TEST STRIP	EACH	1						1								
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	799		799												
40600990	TEMPORARY RAMP	SO YD	84						84								
40603510	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	285.6		285.6												
40603565	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	770.2		770.2												
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	322.4		322.4												
42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT PAVEMENT 10" <i>CONCRETE</i>	SO YD	115		115												
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT. 7 INCH	SO YD	178		178												
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	5849		2235								3614				
42400800	DETECTABLE WARNINGS	SO FT	75		61								14				
44000100	PAVEMENT REMOVAL	SO YD	260		260												
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1434		1434												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	279		279												
44003100	MEDIAN REMOVAL	SO FT	693		693												

X SPECIALTY ITEM

FILE NAME * c:\pwwork\pwwork\pwwork\d0318674\046070-ah-cover.dgn	USER NAME * aubreygs	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.J. RTE. 6658	SECTION ION	COUNTY PEORIA	TOTAL SHEETS 120	SHEET NO. 6
PLOT SCALE * 1/8" = 100.0000'	CHECKED - DATE -	REVISED - REVISED -	CONTRACT NO. 68A70							
PLOT DATE * 10/16/2013	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							