

TREE REMOVAL (6 TO 15 UNITS DIA.)	
LOCATION	UNIT
FARMINGTON RD.	
	12.00
	13.00
	12.00
DRAINAGE DITCH BY KOENIG ON LT. SIDE OF ROAD	11.00
	12.00
	14.00
	10.00
TOTAL	84

TREE REMOVAL (OVER 15 UNITS DIA.)	
LOCATION	UNIT
FARMINGTON RD.	
DRAINAGE DITCH BY KOENIG ON LT. SIDE OF ROAD	32
TOTAL	32

TOPSOIL & SEEDING SUMMARY								
LOCATION	TOPSOIL FURNISH & PLACE, 4"	SEEDING, CLASS 1A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	TEMP. EROS. CNTL. SEED.	HEAVY DUTY EROSION CONTROL BLANKET
	SQ. YD.	ACRE	POUND	POUND	POUND	ACRE	POUND	SQ. YD.
IL 8 - FARMINGTON RD								
RT. STA. 32+11 TO 33+57	374.2	0.08	7.2	7.2	7.2	0.08	32	
LT. STA. 33+75 TO 35+59		0.03	2.7	2.7	2.7	0.03	12	
RT. STA. 37+38 TO 38+20	133.9	0.03	2.7	2.7	2.7	0.03	12	133.9
LT. STA. 39+08 TO STA. 39+44	269.5	0.06	5.4	5.4	5.4	0.06	24	
STERLING AVE.								
LT. STA. 22+19.55 TO 26+86.89 (city participation)	367.7	0.28	25.2	25.2	25.2	0.28	112	
RT. STA. 22+19.55 TO 23+13.18 (city participation)	57	0.02	1.8	1.8	1.8	0.02	8	
RT. STA. 23+50 TO 26+25		0.1	9	9	9	0.1	40	
TOTAL	1202	0.6	54	54	54	0.6	240	134

EARTHWORK SUMMARY				
LOCATION	GRADING & SHAPING DITCHES	EARTH EXCAVATION (WIDENING)	EARTH EXCAVATION	FURNISHED EXCAVATION
	FOOT	CU YD	CU YD	CU YD
IL 8 - FARMINGTON RD.				
RT. STA. 33+00 TO 33+46	60			
LT. STA. 33+75 TO 35+59	184			
LT. STA. 33+50 TO 42+93***		430		
RT. STA. 33+82.66 TO 39+00***		359		
LT. STA. 39+29				100
RT. STA. 39+00 TO LT. STA. 26+00 (STERLING)***		41	3.5	15.8
RT. STA. 34+00 TO 36+91.35***			34	12
RT. STA. 37+38.52 TO 39+00***			35.7	
STEVEY AVE.			64	
STERLING AVE.				
RT. STA. 23+50 TO 26+25	275			
RT. STA. 22+19.55 TO 22+95 (city participation)			3	16
LT. STA. 22+19.55 TO 26+00 (city participation)		41	17.4	114.6
TOTAL	519	871	158	258

***Material is considered non-special waste. Cannot be reused on jobsite.

SPECIAL WASTE PLANS AND REPORT	
LOCATION	LSUM
JOBSITE	1
TOTAL	1

SOIL DISPOSAL ANALYSIS	
LOCATION	EACH
JOBSITE	1
TOTAL	1

NON SPECIAL WASTE DISPOSAL		
LOCATION	TYPE OF REMOVAL	CU YD
IL 8 - FARMINGTON RD.		
RT. STA. 33+80 TO 35+40	STORM SEWER TRENCH	206
LT. STA. 33+50 TO 42+93	WIDENING	430
RT. STA. 34+00 TO 37+80	WIDENING	290
LT. STA. 35+55 TO 36+80	STORM SEWER TRENCH	83
RT. STA. 37+10 TO 38+85	STORM SEWER TRENCH	278
STA. 38+40	STORM SEWER TRENCH	59
LT. STA. 38+40 TO 39+29	STORM SEWER TRENCH	137
RT. STA. 37+80 TO LT. STA. 24+50 (STERLING)	WIDENING	142
LT. STA. 39+29	EARTH EX	151
RT. STA. 34+00 TO 36+91.35	EARTH EX	34
RT. STA. 37+38.52 TO 26+51.02 (STERLING)	EARTH EX	39
STEVEY AVE.	PAVMENT RECONSTRUCTION	64
TOTAL		1913