

EROSION CONTROL			
LOCATION	INLET FILTERS	INLET & PIPE PROTECTION	AGG. DITCH CHECKS
	EACH	EACH	TON
IL 8-FARMINGTON RD.			
RT. STA. 32+34		1	
RT. STA. 34+25	1	1	
RT. STA. 35+40	1		
RT. STA. 36+63	1		
RT. STA. 37+60	1	1	
RT. STA. 38+40	1		
LT. STA. 39+29.42		1	8.7
STERLING AVE.			
LT. STA. 22+32	1		
RT. STA. 22+65.86	1		
RT. STA. 22+72.90	1		
LT. STA. 24+80	1		
LT. STA. 26+27.40	1		
LT. STA. 26+54.93		1	
STEVEVER AVE.			
RT. STA. 10+65.94	1		
RT. STA. 10+58		1	
LT. STA. 10+54.64	1		
RHODORA AVE.			
LT. STA. 10+48.07	1		
<b>TOTAL</b>	<b>13</b>	<b>6</b>	<b>9</b>

TRENCH BACKFILL	
LOCATION	CU YD
IL 8 (FARMINGTON ROAD)	
RT. STA. 34+25 TO 35+40	45.8
RT. STA. 36+63 TO 37+60	27.7
RT. STA. 37+60 TO 38+40	25
STA. 38+40	48.7
RT. STA. 38+40 TO 38+85	8.3
LT. STA. 38+40 TO 38+85	36.3
RHODORA	
10+44.97 TO 10+48.07	25.9
STEVEVER	
STA. 10+54.64 TO 10+65.94	8.3
STERLING AVE. (city participation)	
LT. STA. 22+32 TO 24+80	35.2
LT. STA. 24+80 TO 26+27.40	23.5
STA. 26+27.40	5.8
<b>TOTAL</b>	<b>291</b>

LOCATION	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A4	FILTER FABRIC
	SQ. YD.	SQ. YD.	SQ. YD.
<b>IL 8</b>			
RT. STA. 37+57 TO 37+72	23.6		23.6
LT. 39+29.42 DRAINAGE DITCH		231	231
<b>STERLING AVE.</b>			
RT. STA. 22+65.87 (city participation)	7.4		7.4
LT. STA. 26+47.68 TO 26+65.75	12.3		12.3
<b>TOTAL</b>	<b>43</b>	<b>231</b>	<b>274</b>