PAVEMENT WIDENING SCHEDULE

LOCATION			SUB-BASE GRANULAR MATERIAL, TYPE B 12"	P.C.C. BASE COURSE 8"	P.C.C.BASE COURSE WIDENING 8"
			SQ. YD.	SQ. YD.	SQ. YD.
IL 8-FARMINGTON ROAD					
LT. 33+50.00	TO	LT. 43+00.00	916.3	863.2	
RT. 33+82.66	TO	RT. 34+15.29	62.2	52.5	
RT. 34+15.29	TO	RT. 38+03.04	650.5	565.7	
RT. 38+03.04	TO	RT. 38+94.75	71.1		49.9
STERLING AVE.					
LT. 24+50.08	TO	LT. 25+71.09	86.7		44.4
LT. STA. 25+71.09	TO	RT. 38+94.75 (IL8)	213.4	167.9	
STEVER					
STA. 10+33	TO	STA 10+71.68	160.8	151.6	
TOTAL			**2161**	**1801**	**94**

	HIGH-EARLY-STRENGTH PCC PAVEMENT, 10"	SUB-BASE GRANULAR MATERIAL, TYPE B 6"
LOCATION	**SQ YD.**	**SQ YD.**
STERLING AVE.		
OLD ISLAND	38	38
OLD MEDIAN	77	77
TOTAL	**115**	**115**

AGGREGATE SURFACE COURSE, TYPE B

LOCATION	TON
IL 8 (FARMINGTON RD.)	
LT. STA. 38+85 TO 39+50 (6" depth)	49.3
TOTAL	**49**

AGGREGATE FOR TEMPORARY ACCESS

LOCATION	APPLICATIONS	TON
5 Business @ 8.5 tons per entrance	2	85
TOTAL		**85**

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 7"

LOCATION	SQ YD.
IL 8 (FARMINGTON RD.)	
RT. STA. 35+05.76	78.7
RT. STA. 35+40	26.4
RT. STA. 35+71.34	72.5
TOTAL	**178**

PORTLAND CEMENT CONCRETE SIDEWALK 4"

LOCATION	SQ FT
IL 8 (FARMINGTON RD.)	
RT. STA. 33+91.00 (IL 8) TO RT. STA. 34+74.34 (IL 8)	582
RT. STA. 36+02.64 (IL 8) TO RT. STA. 36+91.33 (IL 8)	586.7
RT. STA. 37+39.04 (IL 8) TO LT.26+56.18 (STERLING)	1066
STERLING AVE.	
LT. STA. 22+19.55 TO LT STA. 26+56.18 (city participation)	3108
RT. STA. 22+19.55 TO 22+94.38 (city participation)	506
TOTAL	**5849**

DETECTABLE WARNINGS

LOCATION	SQ FT
IL 8 (FARMINGTON RD.)	
RT. STA. 33+92.80	14
RT.STA. 36+83.70	37
RT.STA. 37+45.31	24
STERLING AVE.	
RT. STA. 22+94.38 (city participation)	14
TOTAL	**75**