

PAVEMENT REMOVAL	
LOCATION	SQ YD
RHODORA AVE.	
RT. STA. 10+13.9 TO 10+33	10.10
LT. STA. 10+13.9 TO 10+48.1	29.83
STEVER	
STA. 10+18.10 TO STA. 10+71.68	220.40
TOTAL	260

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	SQ YD
FARMINGTON RD.	
RT. 34+09.80 TO RT.10+71.68 (BEHIND PROP. SIDEWALK)	590.70
LT. 35+55.89 TO LT. 38+84.98	540.95
LT. 39+47.12 TO LT. 41+75.00	302.50
TOTAL	1434

COMB. CURB & GUTTER REMOVAL	
LOCATION	FOOT
FARMINGTON RD.	
LT. STA. 10+71.68 (STEVEER) TO RT. STA. 39+03.55 (IL 8)	215.7
STEVEER AVE.	
RT. STA. 10+39.61 TO RT. STA. 10+71.68	32.0
RHODORA AVE.	
RT. STA. 10+36.88 TO 10+68.06	31.2
TOTAL	279

MEDIAN REMOVAL	
LOCATION	SQ. FT.
STERLING AVE.	
STA. 25+93.51 TO STA. 26+91.28	693.43
TOTAL	693

CHAIN LINK FENCE REMOVAL AND RE-ERECTED	
LOCATION	FT.
FARMINGTON RD.	
RT. STA. 32+34	20
TOTAL	20

PAVED SHOULDER REMOVAL	
LOCATION	SQ YD
FARMINGTON RD.	
RT. STA. 33+00 TO RT.STA. 33+51.70	35.6
RT. STA. 33+95.71 TO RT. STA. 36+95.94	389.0
LT. STA. 33+50 TO LT. STA. 43+00.0	637.2
STERLING AVE.	
LT. STA. 22+19.55 TO LT. STA. 24+67***	215.8
LT. STA. 24+67 TO LT. STA. 27+18.30	183.8
RT. STA. 22+19.55 TO RT. STA.22+94.38***	67.7
TOTAL	1529
***CITY PARTICIPATION	

CLASS D PATCHES, TYPE 3, 12"	
LOCATION	TOTAL SQ. YD.
IL 8 (FARMINGTON RD.)	
STA. 38+40 @ PROP. 30" STORM SEWER	49
STERLING AVE.	
STA. 26+34 @ 18" STORM SEWER (city participation)	21
TOTAL	70

PIPE CULVERT REMOVAL		
LOCATION	PIPE SIZE AND TYPE	FOOT
FARMINGTON RD.		
RT. 37+13.88 TO 37+55.82	PVC 8"	47.6
LT. 39+29.42 (RCC 54")	RCCP 54"	15
STEVEER AVE.		
LT. 10+39.78 TO RT. 10+54.70	RCCP 12"	36.8
LT. 10+39.78 TO LT. 10+55.50	PVC 10"	15.3
TOTAL		115

REMOVING MANHOLES	
LOCATION	EACH
FARMINGTON RD.	
RT.STA.37+13.38	1
TOTAL	1

REMOVING INLETS	
LOCATION	EACH
STEVEER AVE.	
RT.STA.10+54.70	1
FARMINGTON RD.	
RT.STA. 37+30.08	1
RHODORA AVE.	
RT. STA. 10+34.2	1
TOTAL	3

ISLAND PAVEMENT REMOVAL	
LOCATION	SQ YD
STERLING AVE.	
STA. 26+83	37.7
TOTAL	38
*REMOVAL AREA'S MATCH LIMITS OF EXISTING ISLANDS	

LOCATION	REMOVE EXISTING SIGN COMPLETE	REMOVE EXISTING CONCRETE FOUNDATION
	EACH	EACH
FARMINGTON RD.		
RT. STA. 36+92.83 (BEER SIGN)	1	
RT. STA. 36+84.27 (3'x3'x1')		1
SEE SIGNAL PLANS		4
TOTAL	1	5