

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				TAZEWELL	TAZEWELL
				0021 RURAL	0021 RURAL
				90% FEDERAL	100% STATE
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	98	98	
44003100	MEDIAN REMOVAL	SQ FT	1318	1318	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1412.7	1412.7	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	17.1	17.1	
48203100	HOT - MIX ASPHALT SHOULDERS	TON	232.3	232.3	
50102400	CONCRETE REMOVAL	CU YD	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	27	27	
54215559	METAL END SECTIONS 24"	EACH	1	1	
60100985	PIPE DRAINS 24"	FOOT	119	119	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1	
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	1.84	1.84	
60605000	COMB. CONC. CURB AND GUTTER, TYPE B-6.24	FOOT	172	172	
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	1622.6	1622.6	