

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				TAZEWELL	TAZEWELL
				0021 RURAL	0021 RURAL
				90% FEDERAL	100% STATE
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	7	
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	10	10	
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	54	54	
82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 W	EACH	2	2	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	91	91	
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1	1	
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15	15	
88040410	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, MAST-ARM MOUNTED	EACH	1	1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
X5420624	PIPE CULVERTS TO BE CLEANED 24"	FOOT	25		25
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	
X8040510	RELOCATE ELECTRIC SERVICE	EACH	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

• SPECIALTY ITEM

FILE NAME c:\temp\68b05\04_68b05-shs-cover.dgn	USER NAME kajshbr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE 100:0000 1/4" = 1'	CHECKED -	REVISED -	693			I20N	TAZEWELL	51	7	
PLOT DATE 10/17/2013	DATE -	REVISED -	CONTRACT NO. 68B05							
ILLINOIS FED. AID PROJECT										