

FILTER FABRIC	
LOCATION	SQ YD
IL 9	
Lt. Sta. 810+67 to 810+72	2.8
Lt. Sta. 813+00 to 813+15	8.3
TOTAL	11.1

HMA BASE COURSE WIDENING 13"	
LOCATION	SQ YD
Northwest Corner	349.4
Southwest Corner	57.1
Southeast Corner	326.5
Lt. Sta. 811+82 (Inlet location)	0.1
TOTAL	733.0

AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
IL 9	
Lt. Sta. 809+25 to 810+67	5.4
County Highway 6	
Sta. 6+60 to 9+00	11.7
TOTAL	17.1

HOT-MIX ASPHALT SHOULDERS	
LOCATION	TON
IL 9	
Lt. Sta. 809+25 to 810+00	11.2
Lt. Sta. 811+98 to 813+00	15.2
Rt. Sta. 809+40 to 809+96	27.8
Rt. Sta. 812+66 to 814+50	85.9
County Highway 6	
Lt. Sta. 811+98 to 813+00	62.2
Rt. Sta. 812+66 to 814+50	29.9
TOTAL	232.3

METAL END SECTIONS 24"	
LOCATION	EACH
IL 9	
LT STA 813+00	1
TOTAL	1

PIPE DRAINS, 24"	
LOCATION	FOOT
IL 9	
LT STA. 811+82 to 813+00 @ .42%	119
TOTAL	119

INLETS, TYPE B, TYPE 3 FRAME & GRATE	
LOCATION	EACH
IL 9	
Lt. Sta. 811+82	1
TOTAL	1

FRAMES AND GRATES TO BE ADJUSTED	
LOCATION	EACH
IL 9	
LT STA 811+56	1
TOTAL	1

CLASS SI CONCRETE (OUTLET)	
LOCATION	CU YD
IL 9	
LT STA 810+72 to 810+84	0.92
LT STA 812+88 to 813+00	0.92
TOTAL	1.84

COMB CONC CURB & GUTTER, TY B-6.24	
LOCATION	FOOT
NW Corner	62
NE Corner	110
TOTAL	172

CONCRETE MEDIAN TY SB-6.24	
LOCATION	SQ FT
IL 9	
RT STA 809+79 to 810+60	739.1
RT STA 810+47 to 811+50	883.5
TOTAL	1622.6

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
Jobsite	3
TOTAL	3

MOBILIZATION	
LOCATION	L SUM
Jobsite	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, STD 701201	
LOCATION	L SUM
Jobsite	1
TOTAL	1