

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% FED 20% TOWNSHIP								
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP								
				0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN								
<del>M4021010</del>	<del>AGGREGATE SURFACE COURSE, TYPE D</del>	<del>M TON</del>	<del>500</del>	<del>500</del>														
M4060085	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO M	229.5	229.5														
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	189.9	189.9														
M4060300	AGGREGATE (PRIME COAT)	M TON	27.6	27.6														
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO M	3335	3335														
M4060990	TEMPORARY RAMP	SO M	1600	1600														
M4062125	LEVELING BINDER (MACHINE METHOD), N50	M TON	330	330														
M4062335	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	M TON	501	501														
M4063080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	M TON	56	56														
M4063260	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	M TON	3128.1	3128.1														
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	502	502														
M4063540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	3061.1	3061.1														
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	453	453														
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SO M	1487	1487														

3

3

2

2 12-30-13

3 1-10-14

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)  
SECTION 28R-1  
SANGAMON COUNTY

SCALE: NONE  
DATE: 06/2013

DRAWN BY: GE  
CHECKED BY: FML