

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	25
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO.		CONTRACT NO. 72501		

3

PAVEMENT SCHEDULE																		
LOCATION			SUB-BASE GRANULAR MATERIAL, TYPE A 200MM	AGGREGATE BASE COURSE, TYPE A 150MM	AGGREGATE BASE COURSE, TYPE A 200MM	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N50	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	INCIDENTAL HOT-MIX ASPHALT SURFACING	STRIP REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE SHOULDERS, TYPE B	BASE COURSE WIDENING 280 MM
STATION	STATION	O/S	SQ M	SQ M	SQ M	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	M	MTON	SQ M
ELM STREET			M3110200	M3510150	M3510200	M4021010	M4060200	M4060300	M4062125	M4062335	M4063080	M4063235	M4063310	M4063540	M4080500	M4430020	M4812000	
0+952	0+990	CL					3.75											494
0+964	0+980	LT													8			
1+010	1+056	CL					4.32											568
1+010	1+074	N/A					2.73		43				65					
1+010	1+056	RT	195					0.37										
1+011	1+056	LT	180					0.34										
1+021	1+071	LT													14			
1+056	1+069	LT			11		0.02				2							
1+056	1+073	RT			41		0.1				6							
1+059	1+074	LT															3.2	
1+072	1+074	RT															0.1	
DIVISION STREET																		
1+010	1+027	CL					2											259
1+010	1+055	N/A					1.8		28				42					
1+011	1+027	LT	82					0.2										
1+011	1+027	RT	77					0.1										
1+027	1+047	LT			27		0.1				4							
1+027	1+047	RT			24		0.0				3							
1+027	1+033	RT															1.2	
1+027	1+046	LT															3.9	
1+045	1+055	RT															1.9	
1+054	1+055	LT															0.1	
N. GRAND STREET																		
1+011	1+059	N/A					2.1		33				50					
1+011	1+042	CL					3											353
1+015	1+042	RT	89					0.2										
1+015	1+042	LT	113					0.2										
1+037	1+054	LT			21		0.0				3							
1+037	1+053	RT			17		0.0				2							
1+037	1+059	RT															4.5	
1+037	1+059	LT															4.6	
RIDGE AVENUE																		
0+960	1+004	N/A					0.4			9			55					
1+025	1+050	N/A					0.3			7			53					
JOBSITE				730														
TOTAL			14482	730	404		189.9	27.6	330	501	56	3128.1	502	3061.1	453	3626	59	13938

3

3 1-10-14

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES F.A.P. ROUTE 668 (DIRKSEN PARKWAY) SECTION 28R-1 SANGAMON COUNTY

SCALE: NONE
DATE: 6/2013

DRAWN BY: RC
CHECKED BY: PML