

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	5

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FEDERAL 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP		
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP		
				0003	0021				0028			
URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN						
28000500	INLET AND PIPE PROTECTION	EACH	63	63								
28000510	INLET FILTERS	EACH	159	159								
40600895	CONSTRUCTING TEST STRIP	EACH	3	3								
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2								
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	43	43								
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	49	49								
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	5	5								
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	13	13								
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	62	62								
60500040	REMOVING MANHOLES	EACH	5	5								
60500050	REMOVING CATCH BASINS	EACH	6	6								
60500060	REMOVING INLETS	EACH	8	8								
63500105	DELINEATORS	EACH	11	11								
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	59	59								

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY
SCALE: NONE
DATE: 06/2013
DRAWN BY: GE
CHECKED BY: FML

14