FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	11

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP
				0003	0021				0028	
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	500	500						
M4060085	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ M	229.5	229.5						
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	189.9	189.9						
M4060300	AGGREGATE (PRIME COAT)	M TON	27.6	27.6						
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	3335	3335						
M4060990	TEMPORARY RAMP	SQ M	80	80						
M4062125	LEVELING BINDER (MACHINE METHOD), N50	M TON	330	330						
M4062335	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	M TON	501	501						
M4063080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	M TON	56	56						
M4063235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	M TON	3128.1	3128.1						
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	502	502						
M4063540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	3061.1	3061.1						
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	453	453						
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	1487	1487						

19

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE: NONE
DATE: 06/2013

DRAWN BY: GE
CHECKED BY: FML