FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	14

CONTRACT NO. 72501

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP
				ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP
				0003	0021				0028	
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
M5510025	STORM SEWER REMOVAL 300MM	METER	47	47						
M5510035	STORM SEWER REMOVAL 375MM	METER	7	7						
M5510045	STORM SEWER REMOVAL 450MM	METER	20	20						
M5930100	CONTROLLED LOW-STRENGTH MATERIAL	CU M	21.4	21.4						
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9						
M6021440	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	5	5						
M6021465	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 15 FRAME AND LID	EACH	34	34						
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7						
M6021612	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2						
M6021665	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 15 FRAME AND LID	EACH	5	5						
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
M6021865	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1						
M6022010	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9						
M6022090	MANHOLES, TYPE A, 2.4M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						

14

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE: NONE
DATE: 06/2013

DRAWN BY: CE
CHECKED BY: FML