FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	19

CONTRACT NO. 72501

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 80% FEDERAL 20% STATE	80% FED 20% ST	80% FED 20% ST.	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	80% STATE 20% TOWNSHIP
					ROADWAY/ STORM SEWER	SIDEWALK CITY	CAPITAL TOWNSHIP SIDEWALK	TRAFFIC SIGNALS ELM	TRAFFIC SIGNALS RIDGE	BIKE LANES CITY	BIKE LANES CAPITAL TOWNSHIP
					0003	0021				0028	
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
*	Z0010688	CAMERA MOUNTING ASSEMBLY	EACH	4				4			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
*	Z0033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	2				1	1		
+	Z0070600	TRAINEES	HOUR	2,000	2,000						
	Z0041500	PLUG EXISTING CULVERTS	EACH	5	5						
+	Z0070604	TRAINEES, TRAINING PROGRAM GRADUATE	HOUR	2,000	2,000						
	MX602314	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2						
	M6022047	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 15 FRAME AND LID	EACH	23	23						
	MX602454	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1						
	M6022099	MANHOLES, TYPE A, 2.4M DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1						
	M6022272	MANHOLES, TYPE A, 2.7M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2						
	MX602554	MANHOLES, TYPE A, 2.7M DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1						
*	MZ069961	STORM SEWER (WATER MAIN REQUIREMENTS) EQUIVALENT ROUND-SIZE ELLIPTICAL 600MM	METER	26.0	26.0						
*	MZ069970	STORM SEWER (WATER MAIN REQUIREMENTS) EQUIVALENT ROUND-SIZE ELLIPTICAL 900MM	METER	24.5	24.5						
	M3565280	BASE COURSE WIDENING 280 MM	SQ M	13938	11,984					1265	689
	MX606368	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-22.30 (SPECIAL)	METER	2477.8	2477.8						

+0042 *SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE: NONE
DATE: 06/2013

DRAWN BY: GE
CHECKED BY: FML