

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	25
STA. TO STA.		ILLINOIS FED. AID PROJECT		
FED. ROAD DIST. NO.		CONTRACT NO. 72501		

PAVEMENT SCHEDULE																		
LOCATION			SUB-BASE GRANULAR MATERIAL, TYPE A 200MM	AGGREGATE BASE COURSE, TYPE A 150MM	AGGREGATE BASE COURSE, TYPE A 200MM	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N50	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	INCIDENTAL HOT-MIX ASPHALT SURFACING	STRIP REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE SHOULDERS, TYPE B	BASE COURSE WIDENING 280 MM
<b>ELM STREET</b>																		
STATION	STATION	O/S	SQ.M	SQ.M	SQ.M	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	MTON	M	MTON	SQ.M
0+952	0+990	CL					3.75											494
0+964	0+980	LT													8			
1+010	1+056	CL					4.32											566
1+010	1+074	N/A					2.73		43				65					
1+010	1+056	RT	195					0.37										
1+011	1+056	LT	180					0.34										
1+021	1+071	LT													14			
1+056	1+069	LT			11		0.02				2							
1+056	1+073	RT			41		0.1				6							
1+059	1+074	LT																3.2
1+072	1+074	RT																0.1
<b>DIVISION STREET</b>																		
1+010	1+027	CL					2											
1+010	1+055	N/A					1.8		28					42				259
1+011	1+027	LT	82					0.2										
1+011	1+027	RT	77					0.1										
1+027	1+047	LT			27		0.1				4							
1+027	1+047	RT			24		0.0				3							
1+027	1+033	RT																1.2
1+027	1+046	LT																3.9
1+045	1+055	RT																1.9
1+054	1+055	LT																0.1
<b>N. GRAND STREET</b>																		
1+011	1+059	N/A					2.1		33					50				
1+011	1+042	CL					3											393
1+015	1+042	RT	89					0.2										
1+015	1+042	LT	113					0.2										
1+037	1+054	LT			21		0.0				3							
1+037	1+053	RT			17		0.0				2							
1+037	1+059	RT																4.5
1+037	1+059	LT																4.6
<b>RIDGE AVENUE</b>																		
0+960	1+004	N/A					0.4			9				55				
1+025	1+050	N/A					0.3			7				53				
<b>JOBSITE</b>																		
				730		500												
<b>TOTAL</b>			14482	730	404	500	189.9	27.6	330	501	56	3128.1	502	3051.1	453	3626	59	13938

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES  
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)  
SECTION 28R-1  
SANGAMON COUNTY

SCALE: NONE  
DATE: 6/2013

DRAWN BY: RC  
CHECKED BY: FML