F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	44
STA.	TO STA.			
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 72501

DRAINAGE STRUCTURE SCHEDULE

LOCATION		INLETS, TYPE A TYPE 8 GRATE	INLETS, TYPE A TYPE 15 F&LID	INLETS, TYPE B TYPE 8 GRATE	INLETS, TYPE B TYPE 15 F&LID	PRECAST REINF. CONCRETE F.E.S 300MM	PRECAST REINF. CONCRETE F.E.S 375MM	PRECAST REINF. CONCRETE F.E.S 450MM	PRECAST REINF. CONCRETE F.E.S 900MM	PRECAST REINF. CONCRETE F.E.S. ELLIPTICAL EQ. ROUND-SIZE 600MM	PRECAST REINF. CONCRETE F.E.S. ELLIPTICAL EQ. ROUND-SIZE 900MM	MANHOLES, T-A 1.2M DIA. TYPE 1 F&CLID	MANHOLES, T-A 1.2M DIA. TYPE 8 GRATE	MANHOLES, T-A 1.2M DIA. TYPE 15 F&LID	MANHOLES, T-A 1.5M DIA. TYPE 1 F&CLID	MANHOLES, T-A 1.5M DIA. TYPE 1 F&CLID RESTRICTOR PLATE	MANHOLES, T-A 1.5M DIA. TYPE 15 F&LID	MANHOLES, T-A 1.8M DIA. TYPE 1 F&CLID	MANHOLES, T-A 1.8M DIA. TYPE 15 F&LID	MANHOLES, T-A 2.1M DIA. TYPE 1 F&CLID	MANHOLES, T-A 2.4M DIA. TYPE 1 F&CLID
DIRKSEN PARKWAY		60236200	60237000	60240301	60240320	M542E112	M542E116	M542E120	M542E144	M542E628	M542E644	M6021410	M6021440	M6021465	M6021610	M6021612	M6021665	M6021810	M6021865	M6022010	M6022090
STATION	OFFSET	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
6+456.3	10.49 RT		1																		
6+456.3	14.74 RT												1								
6+487.5	11.01 RT		1																		
6+487.5	15.24 RT												1								
6+500.0	11.22 RT		1																		
6+500.0	15.39 RT												1								
6+519.0	11.53 RT		1																		
6+519.0	15.64 RT												1								
6+547.1	11.12 RT											1									
6+560.8	11.15 RT											1									
CARPENTER STREET																					
STATION	OFFSET																				
0+938.5	5.88 RT					1															
0+944.0	6.05 LT	1																			
0+955.0	6.65 LT			1																	
0+955.0	8.14 RT			1																	
0+971.8	6.27 LT													1							
0+971.8	6.27 RT													1							
0+974.9	10.41 RT		1																		
0+980.0	6.95 LT													1							
1+022.5	6.26 LT				1																
1+025.0	6.26 LT				1																
1+025.0	6.27 RT				1																
1+025.0	10.41 LT		1																		
ENOS AVENUE																					
STATION	OFFSET																				
0+919.4	5.07 LT					1															
0+926.6	5.04 RT					1															
0+937.5	5.92 LT			1																	
0+950.0	6.89 LT													1							
0+950.0	6.47 RT				1																
0+971.4	6.47 LT				1																
0+980.0	11.04 LT				1																
1+025.0	10.08 LT													1							
1+028.5	6.26 RT				1																
1+028.5	6.27 LT													1							
1+028.5	10.42 RT		1																		
ELM STREET																					
STATION	OFFSET																				
0+925.0	5.72 RT	1																			
0+925.0	2.13 LT																			1	
0+925.0	6.73 LT			1																	
0+946.0	7.75 LT	1																			
0+981.8	7.06 RT																				
0+983.4	2.13 LT																	1			
0+983.4	7.10 LT																				
0+983.4	13.08 LT		1																		
1+016.7	7.14 RT																				
1+016.9	7.51 LT																				
DIVISION STREET																					
STATION	OFFSET																				
1+017.0	7.12 RT																				
1+017.5	7.15 LT																				
1+039.4	5.69 LT	1																			
N. GRAND AVENUE																					
STATION	OFFSET																				
1+015.8	8.61 RT																				
1+015.9	9.07 LT																				
TOTAL		43	49	5	13	3	1	4	1	1	1	9	5	34	7	2	5	1	1	9	2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE: NONE — DRAWN BY: RC

DATE: 6/2013 — CHECKED BY: FML