NOTE:
SEE DRAINAGE PLANS FOR STATION, OFFSET, AND ELEVATION INFORMATION FOR PROPOSED CURB AND GUTTER SECTIONS BEYOND PROPOSED SIDEWALK. ALL CURB AND GUTTER POINTS ARE CALLED OUT TO THE TOP OF FACE OF CURB.

BM WS-1 CHSLD 'D' ON SE CORNER OF THE LIGHT POLE SOUTH FOUNDATION OF THE "GAS FOR LESS" STA. 5+956.24, 15.74m LT, ELEV 181.111m

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
668	28R-1	SANGAMON	354	69
STA. 5+880.000	TO STA. 6+055.000			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 72501

MATCH LINE STA. 5+880
SEE SHEET 67

MATCH LINE STA. 6+055
SEE SHEET 71

MATCH LINE STA. 0+959
SEE SHEET 89

UNION PEOPLE PRODUCTS INC.
PARCEL NO. 6271115

NATHAN YOUSIF
PARCEL NO. 6271116

RANDY J. TRANQUILLI
PARCEL NO. 6271117

MANICHANH & SOMSAVATH MAHNEE
PARCEL NO. 6271118

MICHAEL S. KAPSHANDY
PARCEL NO. 6271143

E. EARL ROLAND
PARCEL NO. 6271142

MICHAEL J. O'HAGAN
PARCEL NO. 6271144

DARIN J. & LEANNE BRAUER
PARCEL NO. 6271166

F.A.P. RTE. 668
(DIRKSEN PARKWAY)

ELM STREET

SEC 25, T16N, R5W, 3RD P.M.

EXISTING SIGN TO BE MAINTAINED DURING CONSTRUCTION

PROPOSED CONC. CURB & GUTTER, TYPE B-15.30 (TYPICAL)

PROPOSED CONC. CURB & GUTTER, TYPE B-22.30 (SPECIAL) (TYPICAL)

PROPOSED CONC. CURB & GUTTER, TYPE B-15.60

PROPOSED SIDEWALK 1.5m (TYP.)

PROPOSED SIDEWALK 1.5 m (TYP.)

C.E. TO BE CLOSED

LIMITS OF IMPROVEMENT STA. 1+074.010

NOTE 1:

STORM SEWER REMOVE AND REPLACE PAV'T PATCHING, TY 300MM - 12.4 SQM

0 5 10 20
SCALE = 1 : 250

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ROADWAY PLANS
F.A.P. ROUTE 668 (DIRKSEN PARKWAY)
SECTION 28R-1
SANGAMON COUNTY

SCALE 1 : 250 DRAWN BY RK
DATE 06/2013 CHECKED BY FML

LIN ENGINEERING LTD., 576 OAKMONT LANE, WESTMONT, ILLINOIS 60559 (630)-323-5168 WWW.LINENG.COM