

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTR. CODE | |
|-----------------|---|---------------|----------------|---|--|
| | | | | 90% FED 10% STATE ROADWAY 0005 NONE | |
| 35501324 | HOT-MIX ASPHALT BASE COURSE, 10" | SQ YD | 652 | 652 | |
| X4000115 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | Pounds | 125,172 | 125,172 | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 2813 | 2813 | |
| 40600990 | TEMPORARY RAMP | SQ YD | 1529 | 1529 | |
| 40603243 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 | TON | 39723 | 39723 | |
| 40603345 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 14926 | 14926 | |
| 44000151 | HOT-MIX ASPHALT SURFACE REMOVAL, 1/2" | SQ YD | 77678 | 77678 | |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 22415 | 22415 | |
| 44000161 | HOT-MIX ASPHALT SURFACE REMOVAL, 3" | SQ YD | 2293 | 2293 | |
| 44000162 | HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" | SQ YD | 96970 | 96970 | |
| 44000167 | HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2" | SQ YD | 80387 | 80387 | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 100 | 100 | |
| 44200525 | CLASS A PATCHES, TYPE I, 8 INCH | SQ YD | 30 | 30 | |

2

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTR. CODE | |
|-----------------|------------------------------------|--------------|----------------|---|--|
| | | | | 90% FED 10% STATE ROADWAY 0005 NONE | |
| 44200529 | CLASS A PATCHES, TYPE II, 8 INCH | SQ YD | 60 | 60 | |
| 44200929 | CLASS B PATCHES, TYPE I, 8 INCH | SQ YD | 20 | 20 | |
| 44200934 | CLASS B PATCHES, TYPE II, 8 INCH | SQ YD | 40 | 40 | |
| 44201299 | DOWEL BARS 1 1/2" | EACH | 170 | 170 | |
| 44213000 | PATCHING REINFORCEMENT | SQ YD | 90 | 90 | |
| 44213100 | PAVEMENT FABRIC | SQ YD | 150 | 150 | |
| 44213200 | SAW CUTS | FOOT | 1400 | 1400 | |
| 44213204 | TIE BARS 3/4" | EACH | 6 | 6 | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 11288 | 11288 | |
| 48203042 | HOT-MIX ASPHALT SHOULDERS, 11 1/4" | SQ YD | 60 | 60 | |
| 48203047 | HOT-MIX ASPHALT SHOULDERS, 12 1/2" | SQ YD | 40 | 40 | |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 15073 | 15073 | |
| 63500105 | DELINEATORS | EACH | 226 | 226 | |
| 64200116 | SHOULDER RUMBLE STRIPS, 16 INCH | FOOT | 110303 | 110303 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 8 | 8 | |

△

Rev.

* ITEM REQUIRES SPECIAL PROVISION

| | | | | | | | | | | |
|------------------------------------|----------------|-----------------------------|---|-----------------------|-----------|----------------|---------|----------|--|-----------|
| USER NAME : sparkga | DESIGNED - BTM | REVISED - △ 10/28/13 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| PLOT SCALE : 2.0000' / in. | DRAWN - BTM | REVISED - △ 10/29/13 | | | | 1-72 | * | SANGAMON | 194 | 16 |
| PLOT DATE : Sep-26-2013 07:43:11AM | CHECKED - JSA | REVISED - | | SCALE: | SHEET NO. | OF SHEETS | STA. | TO STA. | * (84-10-1)RS-3, (84-10-2)RS-4 CONTRACT NO. 72C90 ILLINOIS FED. AID PROJECT | |