

PAVEMENT MARKING SCHEDULE

LOCATION	STATION	TO	STATION	LENGTH (FT)	MODIFIED URETHANE PVT MKG- LINE 5"		PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 5"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 6"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 8"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LINE 12"	PREF. PLASTIC PVT. MKG, TY. B INLAID-LTRS. & SYMB.	RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PVT MARKER REMOVAL	DELINEATORS	SHORT-TERM PVT MKG	WORK ZONE PVT. MARKING REM.
					WHITE (FT)	YELLOW (FT)	(FT)	(FT)	(FT)	(FT)	(SQ FT)	(EACH)	(EACH)	(EACH)	(FT)	(SQ FT)
MECHANICSBURG RD. RAMP A																
	100+00.00	TO	103+01.80	302	302							15	15	2	54	18
	103+01.80	TO	106+62.40	361	361			361				38	38	5	65	21
	106+62.40	TO	118+90.80	1,228	1,228	1,228								12	221	73
MECHANICSBURG RD. RAMP B																
	201+54.20	TO	214+89.00	1,335	1,335	1,335								21	240	79
	214+89.00	TO	219+98.00	509	509			509						6	92	30
	219+98.00	TO	226+50.00	652	652									6	117	39
MECHANICSBURG RD. RAMP C																
	300+00.00	TO	303+02.40	302	302							15	15	2	54	18
	303+02.40	TO	306+62.40	360	360			360				38	38	5	65	21
	306+62.40	TO	319+02.40	1,240	1,240	1,240								12	223	74
MECHANICSBURG RD. RAMP D																
	401+35.20	TO	412+78.00	1,143	1,143	1,143								21	206	68
	412+78.00	TO	417+88.00	510	510			510						6	92	30
	417+88.00	TO	424+36.40	648	648									6	117	39
TR 420 RAMP A																
	100+00.00	TO	103+02.30	302	302							15	15	2	54	18
	103+02.30	TO	106+64.41	362	362			362				38	38	5	65	22
	106+64.41	TO	119+42.20	1,278	1,278	1,278								22	230	76
TR 420 RAMP B																
	201+37.60	TO	213+41.00	1,203	1,203	1,203								20	217	71
	213+41.00	TO	218+50.00	509	509			509						6	92	30
	218+50.00	TO	224+99.80	650	650									6	117	39
TR 420 RAMP C																
	300+00.00	TO	303+02.50	303	303							15	15	2	54	18
	303+02.50	TO	306+62.40	360	360			360				38	38	5	65	21
	306+62.40	TO	317+93.20	1,131	1,131									22	204	67
TR 420 RAMP D																
	401+39.70	TO	411+64.00	1,024	1,024	1,024								20	184	61
	411+64.00	TO	417+13.00	549	549			549						6	99	33
	417+13.00	TO	423+40.60	628	628									6	113	37
TOTALS =					65,029	63,495	15,509	933	7,100	748	130	1,763	1,763	226	13,647	4,504

USER NAME = sparkgw PLOT SCALE = 2.0000' / in. PLOT DATE = Sep-05-2013 07:48:43AM	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - BTM	REVISED -						I-72	*	SANGAMON	194	28
	CHECKED - JSA	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				* (84-10-1)RS-3, (84-10-2)RS-4		CONTRACT NO. 72C90		ILLINOIS FED. AID PROJECT
DATE - 12/19/12	REVISED -											