



EXIST. CURVE C6 (I-72)
 PI STA. = 256+98.47
 $\Delta = 9^\circ 39' 43''$ (RT)
 $D = 0^\circ 30' 00''$
 $R = 11,459.16'$
 $T = 968.49'$
 $L = 1,932.39'$
 $E = 40.85'$
 $e = 1.67\%$
 $T.R. = 67.50'$
 $S.E. RUN = 75.00'$
 $P.C. STA. = 247+29.98$
 $P.T. STA. = 266+62.37$

SEE NOTE #13, GENERAL NOTES, SHT. 2

PAVEMENT MARKING LEGEND

- ① PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 5" (30' SKIP, 10' DASH)
- ② PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID YELLOW)
- ③ PR URETHANE PAVEMENT MARKING, LINE 5" (SOLID WHITE)
- ④ PR URETHANE PAVEMENT MARKING, LINE 6" (SOLID WHITE)
- ⑤ PR URETHANE PAVEMENT MARKING, LINE 6" (6' SKIP, 2' DASH)
- ⑥ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 8" (SOLID WHITE)
- ⑦ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 12" (SOLID WHITE)
- ⑧ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LINE 24" (SOLID WHITE)
- ⑨ PR PREFORMED PLASTIC PAVEMENT MARKING, TYPE B (INLAID), LETTERS & SYMBOLS (SOLID WHITE)
- ▷ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, WHITE
- ◀ PR RAISED REFLECTIVE PAVEMENT MARKER, ONE-WAY, AMBER



USER NAME = sparkgw	DESIGNED - BTM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN SHEETS				F.A.I. RTE. I-72	SECTION #	COUNTY SANGAMON	TOTAL SHEETS 194	SHEET NO. 47
	DRAWN - BYM	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.	# 184-10-1RS-3, (84-10-2)RS-4		CONTRACT NO. 72C90	ILLINOIS FED. AID PROJECT	
PLOT SCALE = 100.0000' / in.	CHECKED - JSA	REVISED -										
PLOT DATE = Sep-06-2013 09:21:17AM	DATE - 12/19/12	REVISED -										