

DRAINAGE SCHEDULE															
LOCATION	STATION	TO	STATION	PIPE CULV REM (FOOT)	PLUG EXST CULVERTS (EACH)	INLETS TO BE ADJUSTED (EACH)	FILLING INLETS (EACH)	FILLING EXST CULVERTS (EACH)	REM INLET BOX (EACH)	STONE RIPRAP CL A4 (SQ YD)	FILTER FABRIC FOR RIPRAP (SQ YD)	TY D INLET BOX (STD 609006) (EACH)	METAL END SECTIONS, 12" (SQ FT)	TRENCH BACKFILL (CU YD)	PIPE CULV. CL A, TY 1, 12" (FOOT)
<b>MECHANICSBURG RD. MAINLINE</b>															
	95+24.80	RT					1								
	95+24.80	LT			1										
	98+38.40	LT								92	92	1	1		11
	98+49.13	RT								92	92	1	1		11
	98+69.50	LT						1							
	98+69.50	LT	TO	98+80.80	RT	60								11	
	98+80.80	RT							1						
	98+83.80	RT				1									
	101+35.40	LT							1						
	101+35.40	LT	TO	101+45.70	RT	60								11	
	101+45.70	RT							1						
	101+51.50	RT				1									
	101+66.88	LT								92	92	1	1		11
	101+77.54	RT								92	92	1	1		11
	104+80.20	LT					1								
	104+80.20	RT				1									
<b>TR 420 MAINLINE</b>															
	288+98.00	CL					1								
	294+27.70	LT				1		1							
	294+27.70	LT	TO	294+78.00	LT			1							
	294+78.00	LT													
	298+13.21	LT								92	92	1	1		11
	298+13.21	RT								92	92	1	1		11
	298+43.70	LT							1						
	298+43.70	LT	TO	298+40.80	RT	59								12	
	298+40.80	RT							1						
	298+45.20	RT				1									
	301+15.10	RT				1									
	301+16.40	LT							1						
	301+16.40	LT	TO	301+16.40	RT	57								12	
	301+16.40	RT							1						
	301+47.40	LT								92	92	1	1		11
	301+47.40	RT								92	92	1	1		11
	304+92.00	LT					1								
	304+93.00	LT	TO	305+30.50	LT			1							
	305+30.50	LT							1						
	305+30.50	RT				1									
	309+98.00	CL					1								
<b>TOTALS =</b>				236	8	2	6	2	8	736	736	8	8	46	88

USER NAME : sparksg	DESIGNED - BTM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.I. RTE. 1722	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 194	SHEET NO. 83
PLOT SCALE : 2.0000' / in.	DRAWN - BTM	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	* (84-10-1RS-3,84-10-2RS-4)BR.1	CONTRACT NO. 72C90		
PLOT DATE : Sep-06-2013 09:11:54M	CHECKED - JSA	REVISED -							ILLINOIS FED. AID PROJECT			
	DATE - 12/19/12	REVISED -										