



Notes:
 Hatched area indicates Concrete Removal.
 Existing reinforcement bars extending into the new construction shall be cleaned, straightened and incorporated into the new construction. Cost included with Concrete Removal.
 Existing reinforcement bars not extending into the new construction shall be cut off and covered with a 2" layer of cement grout. Cost included with Concrete Removal.
 Elevations based off a datum difference of -0.49' from existing plans.

* Top of Curtain Wall shall be removed to expose the existing rebar to allow access for extension without damaging the existing reinforcement.

FILE NAME TR420 over FAI-72.dgn	USER NAME =	DESIGNED - SAL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CONCRETE REMOVAL, ABUTMENTS OVERPASS RD. (TR-420) OVER F.A.I.-72 - S.N. 084-0154	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
	PLLOT SCALE =	CHECKED - MTH	REVISED -			72		SANGAMON	194	165		
	PLLOT DATE =	DRAWN - TJW	REVISED -			* (84-10-1RS-3, 84-10-2RS-ROBR,I CONTRACT NO. 72C90						
		CHECKED - MTH	REVISED -			FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT						