

**INDEX OF SHEETS**

- 1. COVER SHEET
- 2. INDEX, GENERAL NOTES, STANDARDS, & SIGNATURES
- 3. SUMMARY OF QUANTITIES
- 4.-6. SCHEDULE OF QUANTITIES
- 7.-13. BRIDGE LOCATION MAPS
- 14. BRIDGE PLAN SHEETS

**HIGHWAY STANDARDS**

- 000001-06
- 001006
- 701201-04
- 701400-07
- 701406-08
- 701411-08
- 701446-05
- 701501-06
- 701901-03

**COMMITMENTS**

COMMITMENTS ARE NOT TO BE ALTERED WITHOUT THE WRITTEN APPROVAL OF ALL PARTIES TO WHICH THE COMMITMENT WAS MADE.

- 1. THE RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS CONCERNING ANY MAJOR PLAN CHANGE, TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.

**GENERAL NOTES**

THE CONCRETE SEALER SHALL BE APPLIED TO THE ENTIRE TOP SURFACE OF THE DECK, INCLUDING THE INSIDE FACES AND TOPS OF THE PARAPETS.  
WATER BASED CONCRETE SEALERS WILL NOT BE ALLOWED.

EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT TO PREVENT THE MATERIAL FROM BEING APPLIED TO THE MARKINGS. THE TEMPORARY COVERING SHALL BE REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT, AND PRIOR TO OPENING TO TRAFFIC. COST TO BE INCLUDED WITH CONCRETE SEALER.

<b>DISTRICT SIX</b>	
EXAMINED <u>10/18</u>	20 <u>13</u>
<i>Bill M. Ryan</i> OPERATIONS ENGINEER	
EXAMINED <u>Oct 9</u>	20 <u>2013</u>
<i>Jim Fitch</i> PROJECT IMPLEMENTATION ENGINEER	
EXAMINED <u>October 25</u>	20 <u>13</u>
<i>ARMU</i> PROGRAM DEVELOPMENT ENGINEER	

• D6 BDGE DECK SEALING 2014-2  
•• LOGAN, CHRISTIAN, MONTGOMERY

FILE NAME *	USER NAME * jonesta	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, GENERAL NOTES AND COMMITMENTS</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pw_work\pwidat\jonesta\d8289421\06x	***sh:gnnote.dgn	DRAWN -	REVISED -			VAR	.	** VARIOUS	14	2	
PLOT SCALE * 40.0000 * / in.	CHECKED -	REVISED -				CONTRACT NO. 72E26					
PLOT DATE * Oct-23-2013 02:14:13PM	DATE -	REVISED -				ILLINOIS FED. AID PROJECT					