

HOT-MIX ASPHALT RESURFACING, COMMERCIAL AND PRIVATE ENTRANCES							
LOCATION OF ENTRANCE (LOCATIONS ARE SPLIT UP, NORTH, SOUTH)	SURFACE AREA (BY CADD)	SURFACE AREA	HMA SURFACE REMOVAL, BUTT JOINT 40600982	POLYMERIZED HMA SURFACE COURSE, MIX "E", N70 (DEPTH 1.5") 40603540	INCIDENTAL HMA SURFACING (1.5" AVG.) 40800050	AGGREGATE PRIME COAT 40600300	BITUMINOUS PRIME COAT 40600200
	( SQUARE FOOT)	( SQUARE YARD)	( SQUARE YARD)	( TON)	( TON)	( TON)	( TON)
<b>NORTH SIDE OF WABASH AVENUE</b>							
WHITE OAKS MALL, WEST ENTRANCE	2,647.0	294.1	294.1	24.7		0.588	0.112
WHITE OAKS MALL, EAST ENTRANCE	3,012.0	334.7	334.7	28.1		0.669	0.127
STA. 564+01.7	480.0	53.3	53.3		4.5	0.107	0.020
STA. 580+01.9	120.0	13.3	13.3		1.1	0.027	0.005
STA. 584+27.3	93.0	10.3	10.3		0.9	0.021	0.004
STA. 585+65.0	202.0	22.4	22.4		1.9	0.045	0.009
STA. 587+93.6	95.0	10.6	10.6		0.9	0.021	0.004
STA. 588+67.2	177.0	19.7	19.7		1.7	0.039	0.007
STA. 589+34.6	204.0	22.7	22.7		1.9	0.045	0.009
STA. 590+30.2	329.0	36.6	36.6		3.1	0.073	0.014
STA. 591+20.2	141.0	15.7	15.7		1.3	0.031	0.006
STA. 591+95.0	82.0	9.1	9.1		0.8	0.018	0.003
STA. 592+51.1	92.0	10.2	10.2		0.9	0.020	0.004
STA. 596+47.7	102.0	11.3	11.3		1.0	0.023	0.004
STA. 597+55.7	91.0	10.1	10.1		0.8	0.020	0.004
STA. 598+15.9	102.0	11.3	11.3		1.0	0.023	0.004
STA. 598+98.9	81.0	9.0	9.0		0.8	0.018	0.003
STA. 599+53.3	75.0	8.3	8.3		0.7	0.017	0.003
STA. 600+34.41	65.0	7.2	7.2		0.6	0.014	0.003
STA. 601+16.24	102.0	11.3	11.3		1.0	0.023	0.004
STA. 602+81.6	80.0	8.9	8.9		0.7	0.018	0.003
SUB TOTAL (NORTH ENTRANCES) =	8,372.0	930.2	930.2	52.8	25.3	1.860	0.353
<b>SOUTH SIDE OF WABASH AVENUE</b>							
K-MART / STAPLES ENTRANCE	3,765.0	418.3	418.3	35.1		0.837	0.159
STA. 526+27.7	3,036.0	337.3	337.3	28.3		0.675	0.128
STA. 540+12.1 (SPFLD. CLINIC ENTRANCE)	1,002.0	111.3	111.3	9.4		0.223	0.042
STA. 577+80.29	399.0	44.3	44.3		3.7	0.089	0.017
STA. 578+58.82	118.0	13.1	13.1		1.1	0.026	0.005
STA. 579+51.44	113.0	12.6	12.6		1.1	0.025	0.005
STA. 580+36.2	357.0	39.7	39.7		3.3	0.079	0.015
STA. 581+27.1	102.0	11.3	11.3		1.0	0.023	0.004
STA. 581+89.7	93.0	10.3	10.3		0.9	0.021	0.004
STA. 582+40.8	474.0	52.7	52.7		4.4	0.105	0.020
STA. 587+83.0	113.0	12.6	12.6		1.1	0.025	0.005
STA. 588+74.6	88.0	9.8	9.8		0.8	0.020	0.004
STA. 589+26.3	60.0	6.7	6.7		0.6	0.013	0.003
STA. 590+56.5	57.0	6.3	6.3		0.5	0.013	0.002
STA. 591+52.3	164.0	18.2	18.2		1.5	0.036	0.007
STA. 592+37.2	129.0	14.3	14.3		1.2	0.029	0.005
STA. 594+07.2	91.0	10.1	10.1		0.8	0.020	0.004
STA. 594+67.8	146.0	16.2	16.2		1.4	0.032	0.006
STA. 595+93.8	121.0	13.4	13.4		1.1	0.027	0.005
STA. 596+60.7	114.0	12.7	12.7		1.1	0.025	0.005
STA. 597+86.7	126.0	14.0	14.0		1.2	0.028	0.005
STA. 598+66.7	73.0	8.1	8.1		0.7	0.016	0.003
STA. 601+71.5	245.0	27.2	27.2		2.3	0.054	0.010
SUB TOTAL (SOUTH ENTRANCES)	10,986.0	1,220.7	1,220.7	72.8	29.7	2.441	0.464
<b>OVERALL TOTALS =</b>	<b>19,358.0</b>	<b>2,150.9</b>	<b>2,150.9</b>	<b>125.6</b>	<b>55.0</b>	<b>4.302</b>	<b>0.817</b>

TEMPORARY RAMPS				
LOCATION OF SIDE ROAD	LENGTH OF RAMP	WIDTH OF RAMP	AREA OF RAMP	TEMPORARY RAMP
	(FOOT)	(FOOT)	(SQ FOOT)	40600990 (SQUARE YARD)
<b>WABASH AVENUE, BEGIN &amp; END OF PROJECT</b>				
STA. 492+30	66.1	5.0	330.5	36.7
STA. 85+90	59.6	5.0	298.0	33.1
SUBTOTAL =	125.7		628.5	69.8
<b>WABASH AVENUE, E.O.P.</b>				
WHITE OAKS MALL, WEST ENTRANCE	130.0	1.0	130.0	14.4
K-MART ENTRANCE	134.0	1.0	134.0	14.9
WHITE OAKS MALL, EAST ENTRANCE	85.0	1.0	85.0	9.4
STRIP MALL ENTRANCE, SOUTH, STA. 526+28	88.0	1.0	88.0	9.8
DRAWBRIDGE ROAD	93.5	1.0	93.5	10.4
COLONY WEST BOULEVARD	138.0	1.0	138.0	15.3
SPRINGFIELD CLINIC ENTRANCE	66.0	1.0	66.0	7.3
MONTVALE DRIVE	84.0	1.0	84.0	9.3
KIRKLEY LANE	109.0	1.0	109.0	12.1
ROBINHOOD LANE, NORTH LEG	63.0	1.0	63.0	7.0
ROBINHOOD LANE, SOUTH LEG	107.0	1.0	107.0	11.9
SOUTH CORBIN STREET	76.0	1.0	76.0	8.4
LEONARD STREET	73.0	1.0	73.0	8.1
FILMORE STREET	76.0	1.0	76.0	8.4
PARK AVENUE, SOUTH LEG	121.0	1.0	121.0	13.4
SUBTOTAL =	1443.5		1443.5	160.4
<b>SIDE ROADS, ENTRANCES</b>				
ROBBINS ROAD, NORTH LEG	52.6	5.0	263.0	29.2
ROBBINS ROAD, SOUTH LEG	66.6	5.0	333.0	37.0
WEST WHITE OAKS DRIVE, NORTH LEG	37.0 & 25.0	5.0	62.0	6.9
WEST WHITE OAKS DRIVE, SOUTH LEG	23.4 & 35.4	5.0	58.8	6.5
PROJECT OMISSION, STA. 511+70	32.7 & 61.8	5.0	94.5	10.5
PROJECT OMISSION, STA. 515+00	33.8 & 60.2	5.0	94.0	10.4
WHITE OAKS MALL, WEST ENTRANCE	25.7 & 25.2	5.0	52.9	5.9
K-MART ENTRANCE	52.8	5.0	264.0	29.3
WHITE OAKS MALL, EAST ENTRANCE	25.3, 15.5 & 23.6	5.0	64.4	7.2
STRIP MALL ENTRANCE, SOUTH, STA. 526+28	53.0	5.0	265.0	29.4
DRAWBRIDGE ROAD	24.3 & 23.9	5.0	48.2	5.4
COLONY WEST BOULEVARD	22.0 & 22.2	5.0	44.2	4.9
SPRINGFIELD CLINIC ENTRANCE	32.0	5.0	160.0	17.8
MONTVALE DRIVE	55.4	5.0	277.0	30.8
KIRKLEY LANE	57.5	5.0	287.5	31.9
STA. 553+35, LEFT	26.5	5.0	132.5	14.7
ROBINHOOD LANE, NORTH LEG	23.0 & 30.0	5.0	53.0	5.9
ROBINHOOD LANE, SOUTH LEG	24.5 & 25.1	5.0	49.6	5.5
CHATHAM ROAD, NORTH LEG	60.1 & 31.6	5.0	91.7	10.2
CHATHAM ROAD, SOUTH LEG	28.6 & 61.2	5.0	89.8	10.0
SOUTH CORBIN STREET	42.5	5.0	212.5	23.6
LEONARD STREET	39.5	5.0	197.5	21.9
FILMORE STREET	39.0	5.0	195.0	21.7
PARK AVENUE, NORTH LEG	25.0	5.0	125.0	13.9
PARK AVENUE, SOUTH LEG	51.3	5.0	256.5	28.5
SUBTOTAL =	754.3		3771.6	419.1
<b>TOTALS =</b>	<b>2,323.5</b>		<b>5,843.6</b>	<b>649.3</b>

CONCRETE MEDIAN REMOVAL &/OR REPLACEMENT WORK														
LOCATION OF MEDIAN WORK	EX MEDIAN SURFACE LENGTH	EX MEDIAN SURFACE AREA	EX COMBINED MEDIAN, C & G AREA	COMBINATION C & G REMOVAL	PAVEMENT REMOVAL	CONCRETE MEDIAN SURFACE REMOVAL	SUB-BASE GRANULAR MATERIAL, TYPE B	COMB. CONCRETE CURB & GUTTER, TYPE B 6.24	CONCRETE MEDIAN SURFACE, 4"	CONCRETE MEDIAN, TYPE SB-6.24	BASE COURSE (OPTION) DEPTH = 10 1/2"	POLYMERIZED HMA SURFACE COURSE, MIX "E", N70 (DEPTH = 1.5")	AGG PRIME COAT	BIT PRIME COAT
		(BY CADD)	(BY CADD)	44000500	44000100	X4402020	31101000	60605000	60618300	60620000	Z0002900	40603540	40600300	40600200
	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(SQ YD)	(SQ FT)	(TONS)	(FOOT)	(SQ FT)	(SQ FT)	(SQ YD)	(TON)	(TON)	(TON)
<b>WABASH AVENUE</b>														
STA 518+15.26 TO STA 520+28.10	212.84	550.8	1,281.2	425.7		550.8	32.4			43.7	32.4	12.0	0.06	0.01
STA 524+35.35 TO STA 525+89.35	154.00	557.1	1,483.5	308.0		557.1	36.6			86.5	36.6	13.8	0.07	0.01
STA 526+65.81 TO STA 528+28.50	162.69	753.9	1,521.4	325.4		753.9	37.6				37.6	14.2	0.08	0.01
STA 542+49.07 TO STA 547+73.59	524.52	4,702.4	7,368.7	1,049.0		4,702.4	100.0	642.0	1,927.4	658.0	344.6	29.0	0.69	0.13
STA 548+45.87 TO STA 550+53.36	207.49	990.9	2,100.2	415.0		990.9	45.0	60.0	177.9	230.0	171.0	14.4	0.34	0.07
STA 560+18.97 TO STA 561+22.18	103.21	358.0	629.6	206.4		358.0	16.0				70.0	5.9	0.14	0.03
STA 561+22.18 TO STA 562+69.39	147.21	539.5	912.9	294.4		539.5	23.1				18.5	1.6	0.04	0.01
STA 575+00.41 TO STA 575+88.97	88.56	83.2	83.2		89.3	87.0	10.0	139.2	651.0	107.9				
<b>SIDE ROADS / ENTRANCES</b>														
WHITE OAKS MALL, EAST ENTRANCE	22.6	87.8	140.8	45.0		87.8	1.5			45.9	10.7	1.0	0.02	0.01
MONTVALE DRIVE	45.0	182.1	329.8	83.0		182.1	8.3				36.6	3.1	0.07	0.01
<b>TOTALS =</b>				<b>3,151.9</b>	<b>89.3</b>	<b>8,809.5</b>	<b>310.5</b>	<b>841.2</b>	<b>2,756.3</b>	<b>1,944.6</b>	<b>758.0</b>	<b>95.0</b>	<b>1.51</b>	<b>0.29</b>