

RESURFACING SCHEDULE

STATION TO STATION	LENGTH FOOT	AVERAGE PAVEMENT WIDTH FOOT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 TON	TEMPORARY RAMP SQ YD
ILLINOIS 130									
436+00.00 TO 438+63.00	263.0	29.0	847	847	85	1.7	71	131	106.9
438+63.00 TO 443+35.00	472.0	28.0	1468	1468	147	2.9	123	226	
443+35.00 TO 444+33.00	98.0	43.0	468	468	47	0.9	39	72	
444+33.00 TO 446+64.00	231.0	40.0	1027	1027	103	2.1	86	158	
446+64.00 TO 449+15.00	251.0	34.0	948	948	95	1.9	80	146	106.9
449+15.00 TO 451+52.00	237.0	OMISSION							
451+52.00 TO 453+90.00	238.0	34.0	899	899	90	1.8	76	139	106.9
453+90.00 TO 456+40.00	250.0	40.0	1111	1111	111	2.2	93	171	
456+40.00 TO 457+35.00	95.0	47.0	496	496	50	1.0	42	76	
457+35.00 TO 459+50.00	215.0	29.0	693	693	69	1.4	58	107	
462+25.00 TO 465+15.00	290.0	27.0	870	870	87	1.7	73	134	
465+15.00 TO 471+25.00	610.0	26.0	1762	1762	176	3.5	148	271	106.9
INTERCHANGE RAMPS									
EB OFF RAMP	60.0	VAR	381	381	38	0.8	32	59	134.4
EB ON RAMP	85.0	VAR	296	296	30	0.6	25	46	98.7
WB OFF RAMP	80.0	VAR	423	423	42	0.8	36	65	113.1
WB ON RAMP	92.0	VAR	304	304	30	0.6	26	47	98.7
ILLINOIS 121									
WEST APPROACH	110.0	VAR	698	698	70	1.4	59	108	123.3
EAST APPROACH	75.0	VAR	554	554	55	1.1	47	85	123.3
TOTALS	3752.0		13246	13246	1324	26	1113	2040	1119

• D7 HMA RESURFACING 2014-1

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\steffenmk\d0348323\074628-sht-sch.dgn	DRAWN -	REVISED -	116						•	CUMBERLAND	15	7	
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: N/A	SHEET 1	OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 74628			
	PLOT DATE = 10/15/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								