

100% STATE

100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1324	1324		
40600300	AGGREGATE (PRIME COAT)	TON	26	26		
40600990	TEMPORARY RAMP	SQ YD	1119	1119		
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2040	2040		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1113	1113		
44000166	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/4"	SQ YD	12770	12770		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	112	112		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	36	36		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	187	187		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1242	1242		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	63	63		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12972	12972		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	452	452		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	183	183		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	205	205		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12972	12972		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	452	452		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	170	170		

* SPECIALTY ITEM

* D7 HMA RESURFACING 2014-1

FILE NAME :	USER NAME : staffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\staffennk\0340323\074628-shr-seq.dgn	74628-shr-seq.dgn	DRAWN -	REVISED -		SCALE: N/A	SHEET 1 OF 2 SHEETS	STA.	TO STA.	116	CUMBERLAND	15	3
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -		CONTRACT NO. 74628							
	PLOT DATE = 10/15/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							

24