

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0005		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	953	953		
40600300	AGGREGATE (PRIME COAT)	TON	19	19		
40600990	TEMPORARY RAMP	SQ YD	108	108		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	801	801		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	9532	9532		
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	8	8		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	253	253		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	48	48		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	170	170		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	800	800		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0005		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	31.2	31.2		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10467	10467		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	115	115		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	269	269		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	133.3	133.3		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	31.2	31.2		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10467	10467		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	115	115		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	269	269		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	81	81		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		

* SPECIALTY ITEM