

RESURFACING SCHEDULE		LENGTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NTO	LEVELING BINDER (MACHINE METHOD), NTO	AGGREGATE WEDGE SHOULDER, TYPE B	TEMPORARY RAMP
STATION	TO STATION	FOOT	SO YD	SO YD	SO YD	GALLON	TON	TON	TON	TON	SO YD
395+16.00	TO 395+46.00	30.0	80			8	0.1	7	2	2	13
395+46.00	TO 400+00.00	454.0		1211		121	1.2	102	51	20	
400+00.00	TO 409+76.00	976.0		2603		260	2.6	219	109	43	
409+76.00	TO 414+74.00	498.0		1328		133	1.3	112	56	11	
414+74.00	TO 415+04.00	30.0			80	8	0.1	7	2	1	
415+04.00	TO 415+83.00	79.0			398	40	0.4	33	0	6	87
TOTALS			80	5141	478	570	6	479	219	83	101

PAVEMENT MARKING SCHEDULE		LENGTH	PAINT PAVEMENT MARKING - LINE 4" (YELLOW)	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
STATION	TO STATION	FOOT		FOOT	SQ FT
395+16.00	TO 400+00.00	484.0	121	144	16
400+00.00	TO 405+00.00	500.0	125	156	17
405+00.00	TO 410+50.00	550.0	138	168	19
410+50.00	TO 415+50.00	500.0	1000	156	17
TOTALS			1384	624	69