



CULVERT WORK AT RT. STA. 407+23

PIPE CULVERT REMOVAL
 QTY = 50 FOOT

PIPE CULVERTS, CLASS A, TYPE I
 EQUIVALENT ROUND-SIZE 18"
 QTY = 50 FOOT

TRENCH BACKFILL
 QTY = 6 CU YD

PIPE TO BE REMOVED IS AN 18" DIA.
 CMP IN ENTRANCE TO PROPANE COMPANY

CULVERT WORK AT STA. 407+98

PIPE CULVERT REMOVAL
 QTY = 38 FOOT

PIPE CULVERTS, CLASS A, TYPE I
 EQUIVALENT ROUND-SIZE 36"
 QTY = 38 FOOT

PRC FLARED END SECTION EORS 36" = 2 EACH

TRENCH BACKFILL
 QTY = 7 CU YD

PIPE TO BE REMOVED IS A 36" DIA. EORS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ei:\pw\work\p\dot\steffenmk\d0351510\07	4640-sh:plan.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/28/2013	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

PLAN			
SCALE: 20	SHEET 3	OF 4	SHEETS
STA. 405+00	TO STA. 411+00		

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
11	D7 HMA RESURF 2014-4	CLARK	13	10
CONTRACT NO. 74640				
ILLINOIS FED. AID PROJECT				