TRAFFIC SIGNAL GENERAL NOTES

THIS TRAFFIC SIGNAL PROJECT IS LOCATED AT THE INTERSECTIONS OF 12TH STREET & STATE STREET AND 11TH STREET & STATE STREET IN THE CITY OF LAWRENCEVILLE, LAWRENCE COUNTY. THE WORK INCLUDED IN THIS SECTION CONSISTS OF INSTALLING PEDESTRIAN PUSH-BUTTONS AND A WIRELESS VEHICLE DETECTION SYSTEM AT EACH INTERSECTION AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL HARDWARE SHALL BE TIGHTENED AND WELL SECURED. CABLES SHALL BE NEATLY WOUND IN HANDHOLES. CABLES SHALL BE NEATLY TRAINED IN THE CONTROLLER CABINET.

ALL THREADS OF BOLTS USED IN ASSEMBLY OF TRAFFIC SIGNAL COMPONENETS SHALL BE COATED WITH A NON-LEAD BASED ANTI-SEIZE COMPOUND, SIMILAR TO LEAD PLATE, PRIOR TO ASSEMBLY.

THE NUMBER OF CONDUCTORS FOR ELECTRIC CABLES AS SHOWN ON THE PLANS SHALL BE THE MINIMUM NUMBER OF CONDUCTORS FURNISHED FOR EACH LOCATION. THE CONTRACTOR MAY SUBSTITUTE AN ELECTRIC CABLE WITH MORE CONDUCTORS THAN SPECIFIED BUT NO ADDITIONAL CONPENSATION WILL BE MADE FOR THE EXTRA CONDUCTORS.

ALL NEW TRAFFIC SIGNAL WIRING SHALL EXTEND FROM CONTROLLER TO SIGNAL. SPLICES IN HANDHOLES WILL NOT BE ALLOW.

CONTRACTOR SHALL ARRANGE TO HAVE THE MANUFACTURER'S REPRESENTATIVE PRESENT FOR THE WIRELESS VEHICLE DETECTION SYSTEM SET-UP.

INDEX OF SHEETS

1	COVER	SHE	EET			
2	INDEX	OF	SHEETS	AND	GENERAL	NOTES

SUMMARY OF QUANTITIES

PLAN LAYOUT AND BILL OF MATERIALS-12+h & STATE ST PLAN LAYOUT AND BILL OF MATERIALS-11+h & STATE ST

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 5:

000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701006-05 OFF-ROAD OPERATIONS, 2L, 2W, 12' TO 24" FROM PAVEMENT EDGE
701501-06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED

TRAFFIC CONTROL DEVICES 720001-01 SIGN PANEL MOUNTING DETAILS

857001-01 STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES

FILE NAME :		USER NAME = steffenmk	DESIGNED -	REVISED -				ı	NDEX OF SHEETS		F.A.S.	SECTION	COUNTY	TOTAL	٥
c:\pw.work\pwidos\	\stefformk\d0360916\07	4644-sht-plan.dgn	DRAWN -	REVISEO -	STATE OF ILLINOIS	GENERAL NOTES					1807	•	LAWRENCE	5	-
		PLQT SCALE = 20.0000 17 in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION						CONTRAC	T NO.	7		
		PLOT DATE + 10/24/2013	DATE -	REVISED ~		SCALE;	SHEET	OF	SHEETS STA.	TO STA.		ILLINOIS FED.	ATO PROJECT	***************************************	****
										•D7 SIGNAL MODERNIZATION 2014-1					