

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005	0021	TRAFFIC SIG.					0005	0021	TRAFFIC SIG.
CODE NO	ITEM	UNIT		ROADWAY 80% FED 20% STATE	PARK. LANES 50% STATE 50% CITY		CODE NO	ITEM	UNIT		ROADWAY 80% FED 20% STATE	PARK. LANES 50% STATE 50% CITY	TRAFFIC SIG. 80% FED 13.3% STATE 6.7% CITY
20400800	FURNISHED EXCAVATION	CU YD	162	162			44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	966	966		
28100107	STONE RIPRAP, CLASS A4	SO YD	653	653			44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	19371	19371		
28200200	FILTER FABRIC	SO YD	653	653			44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SO YD	7163	4537	2626	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	11	11			44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	21	21		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	33.4	32.3	1.1		44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	30	30		
40600300	AGGREGATE (PRIME COAT)	TON	199	191	8		44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	68	68		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	2168	1947	221		44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	32	32		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1387	1387			44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	505	505		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	711	711			44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	48024	48024		
40600990	TEMPORARY RAMP	SO YD	1042	1042			48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	746	746		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	7189	6968	221		48203100	HOT-MIX ASPHALT SHOULDERS	TON	1172	1172		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	139	139			50105220	PIPE CULVERT REMOVAL	FOOT	76	76		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	47414	47414			54215559	METAL END SECTIONS 24"	EACH	2	2		
							54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	85	85		

12-23-13 1-8-14

FILE NAME =	USER NAME = dintelman.jn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. R.T.C. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pr-work\pilot\dintelman.jn\48287304	4876F47-ent-plan.dgn	DRAWN -	REVISED -			42	102-1R5-3,102-TS	WASHINGTON	46	3
	PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -						CONTRACT NO. 76F47	
	PLOT DATE = 10/18/2013	DATE -	REVISED -						ILLINOIS FED. AID PROJECT	
						SCALE:	SHEET	OF	SHEETS	STA. TO STA.