

# SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021		
CODE NO	ITEM	UNIT		MOCKINGBIRD ROAD	IL015	
72000100	SIGN PANEL - TYPE 1	SQ FT	5	5		
72000200	SIGN PANEL - TYPE 2	SQ FT	20	20		
80300100	LOCATING UNDERGROUND CABLE	FOOT	20		20	
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1		
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	72	72		
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	988	988		
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	281	281		
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	214	214		
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	12	12		
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	9	9		
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1		
85706000	INTERSECTION MONITOR UNIT	EACH	1	1		

SCHEDULE OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021		
CODE NO	ITEM	UNIT		MOCKINGBIRD ROAD	IL015	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1603	1603		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	486	486		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2261	2261		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	25	25		
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1706	1706		
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1	1		
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1	1		
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	1		
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1	1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3	3		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4		