



**DETAIL
CCTV & RADAR VEHICLE DETECTOR**

NOT TO SCALE

LOCATIONS:

ITS ELEMENTS SCHEDULE			
ELEMENT	STA.	EOP OFFSET	# OF LANES
RADAR DETECTION			
005522.0S.99R	1148+69 RT (SB)	30'	4
CAMERA			
557017.0A.36C	832+80 RT (NB)	O.E.50'L.D.	N/A
557017.6A.37C	1375+00 LT (NB)	O.E.50'L.D.	N/A
557019.1A.38C	1294+50 RT (SB)	O.E.50'L.D.	N/A
005519.7A.39C	1263+75 LT (NB)	O.E.50'L.D.	N/A
005522.0A.60C	1148+69 RT (SB)	30'-O.P.50'L.D.	N/A

O.E.50'L.D.=ON EXISTING 50' STEEL POLE WITH CAMERA LOWERING DEVICE
O.P.50'L.D.=ON PROPOSED 50' STEEL POLE WITH CAMERA LOWERING DEVICE

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -
ct:\pw\work\p\dot\prestonme\d0320429\d076g08-shr-ITS.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 10/17/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

CCTV AND RADAR VEHICLE DETECTION MOUNTING DETAIL

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	DIST 8 ITS 2014-1	MADISON	44	9
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO.76G08	