

PATCHING SCHEDULE					
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	PAVEMENT PATCHING,	PAVEMENT PATCHING,	PAVEMENT PATCHING,
			TYPE II, 10 INCH SQ YD	TYPE III, 10 INCH SQ YD	TYPE IV, 10 INCH SQ YD
<b>RAMP "T"</b>					
13+30	35	8			31.1
13+44	60	8			53.3
14+20, LT.	6	8	5.3		
14+20, RT.	6	8	5.3		
<b>ROADWAY "H"</b>					
95+56, LT.	6	8	5.3		
95+56, RT.	6	8	5.3		
102+87	35	7.5			29.2
<b>RAMP "T" / ROADWAY "H" SUBTOTAL</b>			21.3		113.6
<b>ANTICIPATED FAILURES (15%)</b>			3.2		17.0
<b>RAMP "T" / ROADWAY "H" TOTAL</b>			25		131
<b>CAMP JACKSON ROAD / IL ROUTE 157 (LOUISE TO BRIDGE)</b>					
150+90, LT.	15	12		20.0	
150+90, RT.	15	12		20.0	
161+27	30	6		20.0	
162+61, LT.	15	12		20.0	
162+61, RT.	15	12		20.0	
167+29	75	6			50.0
167+56	20	14			31.1
<b>"LOUISE TO BRIDGE" SUBTOTAL</b>				100.0	81.1
<b>ANTICIPATED FAILURES (15%)</b>				15.0	12.2
<b>"LOUISE TO BRIDGE" TOTAL</b>				115	94
<b>CAMP JACKSON ROAD / IL ROUTE 157 (CYNTHIA TO LENORA)</b>					
182+74	50	12			66.7
182+84	70	12			93.3
188+59	30	12			40.0
197+64	40	12			53.3
200+51	30	6		20.0	
203+44, LT.	12	12		16.0	
203+44, RT.	12	12		16.0	
203+75	50	6			33.3
207+78	40	13			57.8
207+92	12	13		17.3	
<b>"CYNTHIA TO LENORA" SUBTOTAL</b>				69.3	344.4
<b>ANTICIPATED FAILURES (15%)</b>				10.4	51.7
<b>"CYNTHIA TO LENORA" TOTAL</b>				80	397
<b>TOTAL</b>			25	195	622

PAVEMENT MARKING SCHEDULE								
LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKERS	
		LETTERS & SYMBOLS SQ FT	4" LINE		8" LINE	12" LINE	TWO WAY AMBER EA	WHITE OPAQUE EA
			WHITE (FT)	YELLOW (FT)	WHITE (FT)	YELLOW (FT)		
<b>RAMP "T"</b>								
12+26 TO 19+40 (SEE PLAN SHEET)	SKIP DASH					48		
	SINGLE SOLID		764			84		10
<b>ROADWAY "H"</b>								
89+96 TO 103+05 (SEE PLAN SHEET)	SKIP DASH					87		
	SINGLE SOLID		1,308	543		417		19
<b>RAMP "T"/ROADWAY "H" TOTAL</b>			2,072	543	636			29
<b>CAMP JACKSON ROAD / IL ROUTE 157 (LOUISE TO BRIDGE)</b>								
142+72 TO 168+36 (SEE PLAN SHEET)	SKIP DASH		10	1,189			128	
	SINGLE SOLID		5,114	4,754				
	DOUBLE SOLID			746				
	DIAGONAL					42		
	LETTERS & SYMBOLS	210						
<b>"LOUISE TO BRIDGE" TOTAL</b>			210	5,124	6,689		42	128
<b>CAMP JACKSON ROAD / IL ROUTE 157 (CYNTHIA TO LENORA)</b>								
182+49 TO 207+98 (SEE PLAN SHEET)	SKIP DASH			589			41	
	SINGLE SOLID		5,100	497				
	DOUBLE SOLID			472				
<b>"CYNTHIA TO LENORA" TOTAL</b>				5,100	1,558		41	
<b>TOTALS</b>		210	12,296	8,790	636	42	169	29

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

FILE NAME = 76G42\_1-sht-quant-schedule-02.dgn  
USER NAME = tbonnell  
MODEL NAME = Default  
PLOT SCALE = 20.0000' / in.  
PLOT DATE = 10/30/2013

DESIGNED - TTB  
DRAWN - TTB  
CHECKED - JAH  
DATE - 10/29/13

REVISED -  
REVISED -  
REVISED -  
REVISED -

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	VARIOUS	ST. CLAIR	18	9
CONTRACT NO. 76G42				
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT				

10/30/2013 9:34:31 AM

\$FILE\$