

**SUMMARY OF QUANTITIES**

100% STATE

CONSTRUCTION CODE

ROADWAY 0005

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	RAMP "T" / ROADWAY "H"	CAMP JACKSON ROAD / IL ROUTE 157	
					(LOUISE TO BRIDGE)	(CYNTHIA TO LENORA)
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	2	4	3
40600300	AGGREGATE (PRIME COAT)	TON	42	9	19	14
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	856	139	431	286
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	997	158	457	382
40600990	TEMPORARY RAMP	SQ YD	578	158	245	175
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,712	278	861	573
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42		21	21
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	20,059		11,717	8,342
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,435	5,435		
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	25	25		
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	195		115	80
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	622	131	94	397
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	14,272	4,046	5,128	5,098
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	121		61	60

14

18/29/2013  
76042-1-shr-quant-summary-01.dgn  
2:56:24 PM

USER NAME = tbonnell	DESIGNED - TTG	REVISED -
MODEL NAME = Default	DRAWN - TTG	REVISED -
PLT SCALE = 20.0000' / in.	CHECKED - JAH	REVISED -
PLT DATE = 10/29/2013	DATE - 10/29/13	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	VARIOUS	ST. CLAIR	18	3
CONTRACT NO. 76042			FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT	