

SUMMARY OF QUANTITIES (CON'T.)

100 % STATE

CONSTRUCTION CODE

ROADWAY 0005

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	RAMP "T" / ROADWAY "H"	CAMP JACKSON ROAD / IL ROUTE 157 (LOUISE TO BRIDGE)	CAMP JACKSON ROAD / IL ROUTE 157 (CYNTHIA TO LENORA)
48203100	HOT-MIX ASPHALT SHOULDERS	TON	717	288	215	214
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	0.30	0.68	1.02
67100100	MOBILIZATION	L SUM	1	0.15	0.34	0.51
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1			1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1			1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	15	15	15
70300100	SHORT TERM PAVEMENT MARKING	FOOT	21,764	3,251	11,855	6,658
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	210		210	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21,086	2,615	11,813	6,658
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	636	636		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	42		42	

14

FILE NAME = 76G42.1-shs-quant-summary-02.dgn
 USER NAME = tbonnell
 MODEL NAME = Default
 PLOT SCALE = 20.0000 1/ in.
 PLOT DATE = 10/29/2013

DESIGNED - TTB	REVISED -
DRAWN - TTB	REVISED -
CHECKED - JAH	REVISED -
DATE - 10/29/13	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	VARIOUS	ST. CLAIR	18	4
FED. ROAD DIST. NO. 8 ILLINOIS FED. AID PROJECT			CONTRACT NO. 76G42	