

ROADWAY SCHEDULE

LOCATION			HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	HOT-MIX ASPHALT SHOULDERS	SHOULDER RUMBLE STRIPS, 16 INCH	AGGREGATE WEDGE SHOULDER, TYPE B	INLETS TO BE ADJUSTED	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 5	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6	GUARDRAIL MARKERS, TYPE A	
STA.	TO	STA.	SO YD	SO YD	SO YD	SO YD	TON	TON	TON	TON	FOOT	TON	EACH	FOOT	EACH	EACH	EACH	
IL 255 NORTHBOUND																		
1692+91.60	TO	1693+21.46	BR APPR		133	22	0.06	1	10	6	60			3	1			
1693+21.46	TO	1695+16.60	HMA	770	134	22	0.38	2	66	36	404	7		215			1	
1783+47.10	TO	1785+42.33	HMA	754	134	22	0.41	2	79	39	398	9		352			6	
1785+42.33	TO	1785+72.10	BR APPR		133	22	0.07	1	12	6	60					2		
BRIDGE OMISSION - SN 060-0278																		
1789+98.68	TO	1790+28.47	BR APPR		129	22	0.04	1	9	5	60		2					
1790+28.47	TO	1792+23.68	HMA	697	130	22	0.26	2	54	32	383	3						
IL 255 SOUTHBOUND																		
1772+97.22	TO	1774+92.62	HMA	1056	212	36	0.40	2	84	41	196	1						
1774+92.62	TO	1775+22.22	BR APPR		174	29	0.05	1	13	4	30		2					
1783+29.76	TO	1785+24.87	HMA	714	134	22	0.29	2	55	32	383	3		184			1	
1785+24.87	TO	1785+54.76	BR APPR		133	22	0.07	1	11	5	60			5	1			
BRIDGE OMISSION - SN 060-0279																		
1789+81.19	TO	1790+10.99	BR APPR		129	22	0.06	1	9	5	60		2				1	
1790+10.99	TO	1791+81.19	HMA	627	130	22	0.26	2	48	28	349	3		144			3	
TOTAL				4618	874	831	285	2.35	18	450	239	2443	26	6	903	2	3	11
USE				4,618	874	831	285	2.4	18	450	239	2,443	26	6	903	2	3	11

PAVEMENT MARKING SCHEDULE

LOCATION			RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"			TEMPORARY PAVEMENT MARKING - LINE 8"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING - LINE 4"			THERMOPLASTIC PAVEMENT MARKING - LINE 8"	RAISED REFLECTIVE PAVEMENT MARKER
STA.	TO	STA.	EACH	FOOT	SOLID WHITE	SKIP-DASH WHITE	SOLID YELLOW	SOLID WHITE	SO FT	SOLID WHITE	SKIP-DASH WHITE	SOLID YELLOW	SOLID WHITE	EACH
					FOOT	FOOT	FOOT	FOOT		FOOT	FOOT	FOOT	FOOT	
IL 255 NORTHBOUND														
1692+91.60	TO	1693+21.46	1	12	30	8	30		27	30	8	30		1
1693+21.46	TO	1695+16.60	2	36	196	49	196		159	196	49	196		2
1783+47.10	TO	1785+42.33	2	36	196	49	196		159	196	49	196		2
1785+42.33	TO	1785+72.10	1	12	30	8	30		27	30	8	30		1
BRIDGE OMISSION - SN 060-0278														
1789+98.68	TO	1790+28.47	1	12	30	8	30		27	30	8	30		1
1790+28.47	TO	1792+23.68	2	36	196	49	196		159	196	49	196		2
					0	0	0			0	0	0		
					0	0	0			0	0	0		
IL 255 SOUTHBOUND														
1772+97.22	TO	1774+92.62	2	36	192	49	196	388.0	417	192	49	196	388	2
1774+92.62	TO	1775+22.22	1	12	30	8	30	60.0	67	30	8	30	60	1
											0			
1783+29.76	TO	1785+24.87	2	36	196	49	196		159	196	49	196		2
1785+24.87	TO	1785+54.76	1	12	30	8	30		27	30	8	30		1
BRIDGE OMISSION - SN 060-0279														
1789+81.19	TO	1790+10.99	1	12	30	8	30		27	30	8	30		1
1790+10.99	TO	1791+81.19	2	32	171	43	171		139	171	43	171		2
TOTAL			18	284	1,327	336	1,331	448	1,394	1,327	336	1,331	448	18
USE			18	284		2,994		448	1,394		2,994		448	18