

CODE NUMBER	PAY ITEM	SN 064-0029	
		100% STATE	
		MASSAC COUNTY	
CONSTRUCTION TYPE CODE - 0014			
		UNIT	TOTAL QUANTITY
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	62
Z0012500	CONCRETE CURB REPAIR	FOOT	22
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	6

PAVING SCHEDULE										
STATION				WATERPROOF MEMBRANE SYSTEM	HMA SURFACE COURSE	HMA SHOULDERS	HMA BASE COURSE WIDENING, 10'	HMA SURFACE REMOVAL - BUTT JOINT	PRIME COAT	
				SQ YD	TON	TON	SQ YD	SQ YD	GALLON	
185+05.00	RT	TO	186+35.38	RT			145			
186+35.38	LT	TO	186+75.38	LT		12	45	151	14	
186+35.38	RT	TO	186+75.38	RT		12	45	151	14	
186+75.38	LT	TO	187+09.08	LT	130	11				
186+75.38	RT	TO	187+09.08	RT	130	11				
187+12.21	LT	TO	188+98.21	LT	718	61				
187+12.21	RT	TO	188+98.21	RT	718	61				
189+01.34	LT	TO	189+41.29	LT	154	13				
189+01.34	RT	TO	189+41.29	RT	154	13				
189+41.29	LT	TO	189+81.29	LT		12	45	151	14	
189+41.29	RT	TO	189+81.29	RT		12	45	151	14	
189+81.29	LT	TO	191+05.50	LT			138			
TOTAL					2004	218	20	463	604	56

PAVEMENT MARKING SCHEDULE									
STATION				PAINT PAVEMENT MARKING - LINE 4'			SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	
				4' SOLID YELLOW	4' WHITE SKIP DASH	4' SOLID WHITE			
				FOOT	FOOT	FOOT			
186+35.38	LT	TO	186+75.38	LT	40.00	10	40.00	4	2
186+35.38	RT	TO	186+75.38	RT	40.00	10	40.00	4	2
186+75.38	LT	TO	187+08.29	LT	32.91	10	32.91	4	2
186+75.38	RT	TO	187+08.29	RT	32.91	10	32.91	4	2
187+08.29	LT	TO	189+02.13	LT	193.84	50	193.84	20	7
187+08.29	RT	TO	189+02.13	RT	193.84	50	193.84	20	7
189+02.13	LT	TO	189+41.29	LT	39.16	10	39.16	4	2
189+02.13	RT	TO	189+41.29	RT	39.16	10	39.16	4	2
189+41.29	LT	TO	189+81.29	LT	40.00	10	40.00	4	2
189+41.29	RT	TO	189+81.29	RL	40.00	10	40.00	4	2
SUBTOTAL					692	180	692	72	30
TOTAL					1564			72	30

STRUCTURAL REPAIR OF CONCRETE SCHEDULE			
WEST ABUTMENT			
LOCATION	SIZE	AREA (SQ FT)	NOTES
SW CORNER	2' X 1'	2	
NW CORNER	5' X 1'	5	
NW CORNER	2.5' X 2'	5	
NW CORNER	5' X 1'	5	CURTAIN WALL
TOTAL		17	
EAST ABUTMENT			
LOCATION	SIZE	AREA (SQ FT)	NOTES
SE CORNER	3' X 5'	15	
SE CORNER	2.5' X 1'	2.5	
SE CORNER	5' X 1'	5	CURTAIN WALL
SE CORNER	2' X 2.5'	5	ABUT CAP
SE CORNER	1' X 2'	2	FACE ABUT CAP
NE CORNER	5' X 1'	5	
NE CORNER	1' X 2.5'	2.5	
NE CORNER	5' X 1'	5	CURTAIN WALL
NE CORNER	2.5' X 1'	2.5	
TOTAL		45	

FILE NAME *	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES AND SCHEDULES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\peridot\edamsam\09253283\064	09253283.dgn	DRAWN -	REVISED -		24	*	MASSAC	16	4			
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -		CONTRACT NO. 78249							
PLOT DATE = 10/15/2013		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	